

MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

Name of Work :- Proposed development work of the garden at ashish complex , bhaindar (w) in M.B.M.C. Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	70.02	ITEM NO.1 Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. SSR 32.33 / 211	54	60	Rupees FiftyFour Paise Sixty Only	SMT	3823.09			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	35.01	ITEM NO. 2 Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete SSR 27.05 / 254	10027	16	Rupees Ten Thousand TwentySeven Paise Sixteen Only	Cu.Mt	351050.87			As Above
3	202.28	ITEM NO. 3 Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. SSR NO. 32.11 / 269	700	64	Rupees Seven Hundred Paise SixtyFour Only	Sq.Mt.	141725.46			As Above
4	69.30	ITEM NO. 4 Providing and laying in position flooring of telephone black/Amba White/Cat bary brown/Rubyred/ Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick SSR 33.34	4244	99	Rupees Four Thousand Two Hundred FortyFour Paise NinetyNine Only	Sq.Mt.	294177.81			As Above

5	2.40	ITEM NO. 5 Providing and applying two coats Apex Ultima Puranature Anti-Pollution Or equivalent approved brand, paint should decomposes organic substances and inorganic gases(NOx, VOC's, CO, SOx,formaldehydes, etc.) in presence of natural or artificial light. It contains Graphene and nanoparticles of titanium oxide. and Absorbs CO2 (4.8 Kilogram/15 l). plaster crack should be filled by Acrylic base Crack seal/Textured Crack filler, Paint has to applied on one coat of Apex Ultima Puranature Anti-Pollution Primer or Equivalent. Warranty Should be given by the Manufaturer The work should be done by the Manufacturer Recommended applicator and he should be able to furnish stage wise onsite technical reports from theconcerned company technologist SSR 50.79/ 346	390	60	Rupees Three Hundred Ninety Paise Sixty Only	Sq.Mt.	937.44			As Above
6	2.40	ITEM NO. 6 Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) SSR NO. 25.72 / 236	16107	86	Rupees Sixteen Thousand One Hundred Seven Paise EightySix Only	Cu.Mt.	38658.86			As Above
7	0.18	ITEM NO.7 Providing and fixing in position TMT-FE- 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. SSR NO. 26.33 / 245	94188	15	Rupees NinetyFour Thousand One Hundred EightyEight Paise Fifteen Only	MT	17083.85			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation