

**MIRA-BHANDAR MUNICIPAL CORPORATION  
SCHEDULE 'B'**

**NAME OF WORK:- Proposed Installation Work of Paver Block In Radha Govind Park Building 'A' C.H.S.L. Near Bhaindar Police Station At Bhaindar (W) in MBMC Area.**

Item No	Quantity as per Sanctioned Estimate	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	450.00	ITEM NO.1 Providing and fixing heavy duty inter locking concrete Gray paving blocks of 60 mm thickness of having a strength of 300 kg/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete. SSR 33.49 / 218	906	38	Rupees Nine Hundred Six Paise ThirtyEight Only	SMT	407871.00			As per Instruction given by Executive Engineer/ Site Engineer during execution of work
2	27.00	ITEM NO. 2 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR 21.02	217	35	Rupees Two Hundred Seventeen Paise ThirtyFive Only	CMT	5868.45			As Above
3	21.32	ITEM NO. 3 TRANSPORTING OF EXCAVATED MATERIALS lead 3.00 k.m. SSR Statement C-1	468	37	Rupees Four Hundred SixtyEight Paise ThirtySeven Only	CMT	9985.65			As Above

Contractor /Agency

No.of Correction :

Executive Engineer  
Mira-Bhaindar Municipal Corporation