

**MIRA-BHANDAR MUNICIPAL CORPORATION**  
**SCHEDULE 'B'**

**Name of work:- Proposed Repairing and Maintanace of Transit Camp and Rental Housing bldg. on an annual basis in MBMC Area. (Two Yearly) (Panel System)**

| Item No | Quantity as per Sanctione | Item of Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Estimated Rate |     |                                                                  | Unit   | Total Amount according to estimated | Specification |         | Additional Specification                                                              |
|---------|---------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----|------------------------------------------------------------------|--------|-------------------------------------|---------------|---------|---------------------------------------------------------------------------------------|
|         |                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | In Figures     |     | In Words                                                         |        |                                     | Clause No     | Page No |                                                                                       |
|         |                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rs.            | Ps. | Rs.                                                              |        |                                     |               |         |                                                                                       |
| 1       | 2                         | 3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 4              | 5   | 6                                                                | 7      | 8                                   | 9             | 10      | 11                                                                                    |
| 1       | 1.00                      | ITEM NO. 1<br>Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means<br>SSR NO. 21.02/153                                                                                                                                                                                                                                                                                                                                                                                                                 | 217            | 35  | Rupees Two Hundred Seventeen Paise<br>ThirtyFive Only            | Cu.Mt. | 217.35                              |               |         | As per Instruction given byExecutive Engineer/ Site Engineer during execution of work |
| 2       | 1.00                      | ITEM NO. 2<br>TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m.<br>SSR statement C1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 468            | 37  | Rupees Four Hundred SixtyEight Paise<br>ThirtySeven Only         | Cu.Mt. | 468.37                              |               |         | As Above                                                                              |
| 3       | 1.00                      | ITEM NO. 3<br>Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.<br>SSR NO. 26.33                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3240           | 42  | Rupees Three Thousand Two Hundred Fourty Paise<br>FourtyTwo Only | Cu.Mt. | 3240.42                             |               |         |                                                                                       |
| 4       | 1.00                      | ITEM NO. 4<br>Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/ quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)<br>SSR NO. 24.10 | 10809          | 86  | Rupees Ten Thousand Eight Hundred Nine Paise<br>EightySix Only   | Cu.Mt. | 10809.86                            |               |         |                                                                                       |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |        |    |                                                                                           |        |           |  |  |  |
|----|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----|-------------------------------------------------------------------------------------------|--------|-----------|--|--|--|
| 5  | 1.00 | ITEM NO.5<br>Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete.<br>SSR NO. 27.05                                                                                                                                                                                                                                                                             | 10027  | 16 | Rupees Ten Thousand<br>TwentySeven Paise<br>Sixteen Only                                  | Cu.Mt. | 10027.16  |  |  |  |
| 6  | 1.00 | ITEM NO. 6<br>Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.<br>SSR NO. 32.11 | 700    | 64 | Rupees Seven Hundred<br>Paise SixtyFour Only                                              | Sq.Mt. | 700.64    |  |  |  |
| 7  | 1.00 | ITEM NO.7<br>Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.<br>SSR NO.32.04                                                                                                                                                                                                                                                                                    | 305    | 40 | Rupees Three Hundred<br>Five Paise Fourty Only                                            | Sq.Mt. | 305.40    |  |  |  |
| 8  | 1.00 | ITEM NO. 8<br>Manually clearing the chockes from under ground drainage line including Inspection chambers with the help of required tools for propre functioning line chamber to chamber etc. complete.<br>SSR 46.54                                                                                                                                                                                                                                                                                                  | 77     | 17 | Rupees SeventySeven<br>Paise Seventeen Only                                               | RMT    | 77.17     |  |  |  |
| 9  | 1.00 | ITEM NO. 9<br>Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete.<br>SSR NO. 23.04                                                                      | 125431 | 95 | Rupees One Lakh<br>TwentyFive Thousand<br>Four Hundred ThirtyOne<br>Paise NinetyFive Only | MT     | 125431.95 |  |  |  |
| 10 | 1.00 | ITEM NO. 10<br>Providing and laying matt finish ceramic tiles of having size 30cmx30cm confirming to I.S.15622/2006 (groupDII-A)nd 7 to 8mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float,filling joint with white/colour cement slurry cleaning curing etc. complete.SSR 33.24                                                                                                                                                                                   | 1633   | 30 | Rupees One Thousand<br>Six Hundred ThirtyThree<br>Paise Thirty Only                       | Sq.Mt. | 1633.30   |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |    |                                                                   |        |         |  |  |  |
|----|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|-------------------------------------------------------------------|--------|---------|--|--|--|
| 11 | 1.00 | ITEM NO. 11<br>Providing and laying ceramic tiles of having size 30 cm. x 30 cm. and confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.<br>SSR NO. 33.25                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 1732 | 95 | Rupees One Thousand Seven Hundred ThirtyTwo Paise NinetyFive Only | Sq.Mt. | 1732.95 |  |  |  |
| 12 | 1.00 | ITEM NO. 12<br>Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window of two tracks with rectangular pipe having overall dimension 63.50 x 38.10 x 1.02 mm at weight 0.547 kg/Rmt. and window frame bottom track section 61.85 x 31.75 x 1.20 mm at weight 0.695 kg/Rmt. Top and side track section 61.85 x 31.75 x 1.30 mm at weight 0.659 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. And handle section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass with all required screws and nuts etc, complete. With colour Anodising with box..<br>SSR NO. 39.37 | 7478 | 0  | Rupees Seven Thousand Four Hundred SeventyEight Only              | Sq.Mt. | 7478.00 |  |  |  |
| 13 | 1.00 | ITEM NO. 13<br>Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.<br>SSR NO. 39.68                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 3640 | 35 | Rupees Three Thousand Six Hundred Fourty Paise ThirtyFive Only    | Sq.Mt. | 3640.35 |  |  |  |
| 14 | 1.00 | ITEM NO. 14<br>Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.<br>SSR NO. 39.09/246                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 4202 | 83 | Rupees Four Thousand Two Hundred Two Paise EightyThree Only       | Sq.Mt. | 4202.83 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |    |                                                                     |        |         |  |  |  |
|----|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|---------------------------------------------------------------------|--------|---------|--|--|--|
| 15 | 1.00 | ITEM NO. 15<br>Providing and laying chequered tiles of approved quality of size 30 cm x 30 cm, confirming to corresponding I.S. for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.<br>SSR 33.66                                                                                                                                                     | 1003 | 0  | Rupees One Thousand Three Only                                      | SMT    | 1003.00 |  |  |  |
| 16 | 1.00 | ITEM NO. 16<br>Providing and Fixing 32 mm thick One piece single moulded puff ABSTRONE BUTADYNE STYRINE (ABS) Door shutter for internal use including toilets made up of outer ABS sheet of 1.2 mm thick having puff insulation of 35 to 40 Kg/Cum.density and 10 mm dia.for steel bars 2 Nos., wooden block to receive fixtures, having M.S. hinges 100 mm length, M.S. handles 150 mm length and 10 mm dia sliding door bolt etc. complete<br>SSR NO. 39.80 | 5723 | 55 | Rupees Five Thousand Seven Hundred TwentyThree Paise FiftyFive Only | Sq.Mt. | 5723.55 |  |  |  |
| 17 | 1.00 | ITEM NO. 17<br>Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.<br>SSR NO. 33.06                                                                                                                                                       | 1329 | 14 | Rupees One Thousand Three Hundred TwentyNine Paise Fourteen Only    | Sq.Mt. | 1329.14 |  |  |  |
| 18 | 1.00 | ITEM NO. 18<br>Providing 25 mm to 30 mm thick partition of polished black kadappa stone slab of approved quality including giving required size and shape etc. Fixing in cement mortar 1:3 curing and cement etc. complete. b) Both side polish.<br>SSR NO. 33.33                                                                                                                                                                                             | 1221 | 45 | Rupees One Thousand Two Hundred TwentyOne Paise FortyFive Only      | Sq.Mt. | 1221.45 |  |  |  |
| 19 | 1.00 | ITEM NO. 19<br>Providing and fixing green marble of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing / moulding the sharp edges wherever necessary, curing, etc. complete.<br>SSR NO. 33.48                                                                                                                                                                                    | 2503 | 34 | Rupees Two Thousand Five Hundred Three Paise ThirtyFour Only        | Sq.Mt. | 2503.34 |  |  |  |
| 20 | 1.00 | ITEM NO. 20<br>Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work previously painted in building including scaffolding, if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.<br>SSR NO. 35.09                                                                                                                                                            | 133  | 0  | Rupees One Hundred ThirtyThree Only                                 | Sq.Mt. | 133.00  |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                     |      |    |                                                                                |        |         |  |  |  |
|----|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|--------------------------------------------------------------------------------|--------|---------|--|--|--|
| 21 | 1.00 | ITEM NO. 21<br>Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.<br>SSR NO. 35.21                                                                                               | 37   | 80 | Rupees ThirtySeven<br>Paise Eighty Only                                        | Sq.Mt. | 37.80   |  |  |  |
| 22 | 1.00 | ITEM NO. 22<br>Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete.<br>SSR NO. 35.26                                                                   | 402  | 67 | Rupees Four Hundred<br>Two Paise SixtySeven<br>Only                            | Sq.Mt. | 402.67  |  |  |  |
| 23 | 1.00 | ITEM NO. 23<br>Providing and applying two coats of flat oil paint of approved colour and shade to internal / external plastered surfaces including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete..<br>SSR.SR.NO 35.12                                                                                                                          | 106  | 5  | Rupees One Hundred Six<br>Paise Five Only                                      | Sq.Mt. | 106.05  |  |  |  |
| 24 | 1.00 | ITEM NO. 24<br>Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.<br>SSR 41.40                                                                                                                                                                                                                                                        | 704  | 55 | Rupees Seven Hundred<br>Four Paise FiftyFive Only                              | No.s   | 704.55  |  |  |  |
| 25 | 1.00 | ITEM NO. 25<br>Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete..<br>SSR.NO.41.63 | 5878 | 95 | Rupees Five Thousand<br>Eight Hundred<br>SeventyEight Paise<br>NinetyFive Only | No.s   | 5878.95 |  |  |  |
| 26 | 1.00 | ITEM NO. 26<br>Providing and fixing 10 cm PVC nahani trap with grating etc. complete.<br>SSR.NO.42.67                                                                                                                                                                                                                                                                                               | 565  | 95 | Rupees Five Hundred<br>SixtyFive Paise<br>NinetyFive Only                      | No.s   | 565.95  |  |  |  |
| 27 | 1.00 | ITEM NO. 27<br>Providing and Fixing of P.V.C. flexible Waste Pipe 32 mm dia.                                                                                                                                                                                                                                                                                                                        | 61   | 95 | Rupees SixtyOne Paise<br>NinetyFive Only                                       | NO     | 61.95   |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |    |                                                                                |        |          |  |  |  |
|----|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----|--------------------------------------------------------------------------------|--------|----------|--|--|--|
| 28 | 1.00 | ITEM NO. 28<br>Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and airtight C. I. cover of 75 kg with lid and frame fixed in cement concrete.<br>SSR.NO.42.10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 16489 | 94 | Rupees Sixteen<br>Thousand Four Hundred<br>EightyNine Paise<br>NinetyFour Only | No.s   | 16489.94 |  |  |  |
| 29 | 1.00 | ITEM NO. 29<br>Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1 Kg per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete<br>SSR.SR.NO 31.04 | 1373  | 24 | Rupees One Thousand<br>Three Hundred<br>SeventyThree Paise<br>TwentyFour Only  | Sq.Mt. |          |  |  |  |
| 30 | 1.00 | ITEM NO. 30<br>Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.<br>SSR.SR.NO 31.05                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 476   | 69 | Rupees Four Hundred<br>SeventySix Paise<br>SixtyNine Only                      | Sq.Mt. | 476.69   |  |  |  |
| 31 | 1.00 | ITEM NO. 31<br>Providing and fixing Bison Pannel<br>SSR.SR.NO.55/375                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 999   | 69 | Rupees Nine Hundred<br>NinetyNine Paise<br>SixtyNine Only                      | Sq.Mt. | 999.69   |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                              |      |    |                                                                            |      |         |  |  |  |
|----|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|----------------------------------------------------------------------------|------|---------|--|--|--|
| 32 | 1.00 | ITEM NO. 32<br>Providing and fixing<br>1st class white glazed earthenware Orissa Type W.C. Pan 580 mm dia<br>including P or S trap cast iron soil and vent pipe upto the outside face of the<br>wall (1:5:1 0) cement concrete bedding 15 mm thick, 10 liter P.V.C. flushing<br>cistern with all necessary pipe connection etc. complete.<br>SSR.SR.NO 42.33 | 7757 | 40 | Rupees Seven Thousand<br>Seven Hundred<br>FiftySeven Paise Fourty<br>Only  | No.s | 7757.40 |  |  |  |
| 33 | 1.00 | ITEM NO. 33<br>Providing and fixing on walls/ ceiling/ floor 50 mm dia. CPVC pipe with<br>necessary fittings, remaking good the demolished portion etc. complete.<br>SSR NO. 42.60/272                                                                                                                                                                       | 778  | 5  | Rupees Seven Hundred<br>SeventyEight Paise Five<br>Only                    | RMT  | 778.05  |  |  |  |
| 34 | 1.00 | ITEM NO.34<br>Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with<br>necessary fittings, remaking good the demolished portion etc. complete.<br>Including removing existing pipe line if necessary and conveying and<br>stacking the same in PWD chowky or as directed etc. complete<br>SSR NO. 42.57/272                                | 393  | 75 | Rupees Three Hundred<br>NinetyThree Paise<br>SeventyFive Only              | RMT  | 393.75  |  |  |  |
| 35 | 1.00 | ITEM NO. 35<br>Providing and Fixing of cPVC Coupling for 25mm dia. SSR Sr No.<br>254                                                                                                                                                                                                                                                                         | 30   | 45 | Rupees Thirty Paise<br>FourtyFive Only                                     | NO   | 30.45   |  |  |  |
| 36 | 1.00 | ITEM NO. 36<br>Providing and Fixing of cPVC Coupling for 40mm dia. SSR Sr<br>No. 256                                                                                                                                                                                                                                                                         | 110  | 25 | Rupees One Hundred<br>Ten Paise TwentyFive<br>Only                         | NO   | 110.25  |  |  |  |
| 37 | 1.00 | ITEM NO. 37<br>Providing and Fixing of Elbow 90 Degree for 50mm dia. SSR Sr No. 275                                                                                                                                                                                                                                                                          | 217  | 35 | Rupees Two Hundred<br>Seventeen Paise<br>ThirtyFive Only                   | NO   | 217.35  |  |  |  |
| 38 | 1.00 | ITEM NO. 38<br>Providing and Fixing of Tee for 50mm dia.. SSR Sr No.<br>281                                                                                                                                                                                                                                                                                  | 430  | 50 | Rupees Four Hundred<br>Thirty Paise Fifty Only                             | NO   | 430.50  |  |  |  |
| 39 | 1.00 | ITEM NO. 39<br>Providing and Fixing of Non return Valve 50 mm diameter SSR Sr No. 347                                                                                                                                                                                                                                                                        | 2785 | 65 | Rupees Two Thousand<br>Seven Hundred<br>EightyFive Paise SixtyFive<br>Only | NO   | 2785.65 |  |  |  |
| 40 | 1.00 | ITEM NO. 40<br>Providing and laying for 150 mm dia salt glazed stoneware pipe including<br>fittings Such as bends, tees, single junction, double junctions laying, jointing<br>(including excavation and refilling the trenches) complete.<br>SSR.NO.42.04                                                                                                   | 433  | 65 | Rupees Four Hundred<br>ThirtyThree Paise<br>SixtyFive Only                 | R.Mt | 433.65  |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |    |                                                              |      |         |  |  |  |
|----|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|--------------------------------------------------------------|------|---------|--|--|--|
| 41 | 1.00 | ITEM NO. 41<br>Providing and laying for 225mm dia. salt glazed S.W. Pipe including fitting such as bends, tees, single junction, double junctions laying, jointing (including excavation and refilling the trenches) complete<br>SSR.SR 42.05                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 489  | 30 | Rupees Four Hundred EightyNine Paise Thirty Only             | R.Mt | 489.30  |  |  |  |
| 42 | 1.00 | ITEM NO. 42<br>Providing, laying and fixing P.V.C. pipe of 110 mm. dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.<br>SSR.SR.NO 42.28                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 935  | 55 | Rupees Nine Hundred ThirtyFive Paise FiftyFive Only          | R.Mt | 935.55  |  |  |  |
| 43 | 1.00 | ITEM NO. 43<br>Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592- 1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete.<br>SSR.SR.NO 42.87 | 597  | 45 | Rupees Five Hundred NinetySeven Paise FourtyFive Only        | R.Mt | 597.45  |  |  |  |
| 44 | 1.00 | ITEM NO. 44<br>Providing and Fixing of Aldrop 300*16mm Chromium Plated.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 222  | 60 | Rupees Two Hundred TwentyTwo Paise Sixty Only                | NO   | 222.60  |  |  |  |
| 45 | 1.00 | ITEM NO. 45<br>Providing and Fixing of Handle125mm M.S. Chromium Plated                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 89   | 25 | Rupees EightyNine Paise TwentyFive Only                      | NO   | 89.25   |  |  |  |
| 46 | 1.00 | ITEM NO. 46<br>Providing and fixing precast R.C.C cover without angle frame for path way of size 0.60 m x 0.75 m as per instructed by Engineering – In - Charge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 2892 | 50 | Rupees Two Thousand Eight Hundred NinetyTwo Paise Fifty Only | SMT  | 2892.50 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                              |     |    |                                                            |          |        |  |  |  |
|----|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|----|------------------------------------------------------------|----------|--------|--|--|--|
| 47 | 1.00 | ITEM NO. 47<br>Providing and fixing 6.00 mm thick ISI mark Asbestos Cement Corrugated sheet roofing including galvanised iron 'J' or 'L' hook bolts galvanised iron band bituminous G.I. washers, galvanised iron clamps, bolts, nuts and scaffolding etc. complete.<br>SSR NO. 38.06/224                                                                                                    | 696 | 15 | Rupees Six Hundred<br>NinetySix Paise Fifteen<br>Only      | SMT      | 696.15 |  |  |  |
| 48 | 1.00 | ITEM NO. 48<br>Providing and laying of Tarpaulin sheet for waterproofing of roof top including all materials and labour complete. (Market Rate)                                                                                                                                                                                                                                              | 149 | 80 | Rupees One Hundred<br>FourtyNine Paise Eighty<br>Only      | SMT      | 149.80 |  |  |  |
| 49 | 1.00 | ITEM NO. 49<br>Dewatering on BHP basis by using water pump including diversion of stream, providing cofferdams, earthern bunds etc. as may be necessary for foundation and other parts of the the works and pumping out water during and after excavation as may be required by using 3.0 BHP pump etc. complete. (prior approval of Superintending Engineer will be necessary)<br>SSR 12.22 | 187 | 95 | Rupees One Hundred<br>EightySeven Paise<br>NinetyFive Only | Hrs      | 187.95 |  |  |  |
| 50 | 1.00 | ITEM NO. 50<br>Cleaning elevated water storage Reservoir within a given period, by using bleaching powder at the rate of 14 gm/sq.m .washing thrice potassium permanganate at the rate of 2.50 gm/sq.m. finally, cleaning washing by using nylon brush, coir string and duster, bailing out water etc. complete. xii) Capacity above 4.00 lakh upto 7.00 lakh .<br>SSR 42.49                 | 44  | 62 | Rupees FourtyFour Paise<br>SixtyTwo Only                   | 1000 LTR | 44.62  |  |  |  |
| 51 | 1.00 | ITEM NO. 51<br>Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete.<br>SSR NO. 35.26                                                            | 309 | 75 | Rupees Three Hundred<br>Nine Paise SeventyFive<br>Only     | Sq.Mt.   | 309.75 |  |  |  |

|    |             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |    |                                                                       |        |          |  |  |  |
|----|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----|-----------------------------------------------------------------------|--------|----------|--|--|--|
| 52 | 1.00        | ITEM NO. 52 Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade). SSR NO. 24.10 | 10932 | 81 | Rupees Ten Thousand Nine Hundred ThirtyTwo Paise EightyOne Only       | Cu.Mt. | 10932.81 |  |  |  |
| 53 | 1.00        | ITEM NO. 53 Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. SSR NO. 26.33                                                                                                                                                                                                                                                                                                                                                                                | 94188 | 15 | Rupees NinetyFour Thousand One Hundred EightyEight Paise Fifteen Only | MT     | 94188.15 |  |  |  |
| 54 | 1.00        | ITEM NO. 54 Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc). 25.72                                                                         | 21026 | 99 | Rupees TwentyOne Thousand TwentySix Paise NinetyNine Only             | Cu.Mt. | 21026.99 |  |  |  |
| 55 | ANNEXURE -D |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |    |                                                                       |        |          |  |  |  |
| 56 | 1.00        | Item No.1 (CSR:1-1-9) Supplying & erecting HMS PVC conduit 25mm dia. with necessary accessories in wall/floor with chiselling appropriately as per specification no. WG-MA/CC.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 116   | 0  | Rupees One Hundred Sixteen Only                                       | Mtr    | 116.00   |  |  |  |
| 57 | 1.00        | Item No.2 (CSR:1-2-2) Supplying and erecting 25mm dia. corrugated flexible polypropylene conduit                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 19    | 0  | Rupees Nineteen Only                                                  | Mtr    | 19.00    |  |  |  |

|    |      |                                                                                                                                                                                                                                                                |     |    |                                                 |      |        |  |  |  |
|----|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|----|-------------------------------------------------|------|--------|--|--|--|
| 58 | 1.00 | Item No.3 (CSR:1-3-1)<br>Supplying & erecting mains with 2 x 1.5 sq.mm F.R. solid copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No. WG-MA/BW                                       | 46  | 0  | Rupees FourtySix Only                           | Mtr  | 46.00  |  |  |  |
| 59 | 1.00 | Item No.4 (CSR:1-3-2)<br>Supplying & erecting mains with 2x2.5 sq.mm F.R copper PVC insulated wire laid in provided coduit / trunking/ inside pole/Bus bars or any other places. as per specification No: WGMA/ BW                                             | 71  | 0  | Rupees SeventyOne Only                          | Mtr  | 71.00  |  |  |  |
| 60 | 1.00 | Item No.5 (CSR:1-3-3)<br>Supplying & erecting mains with 2x4 sq.mm F.R copper PVC insulated wire laid in provided coduit / trunking/ inside pole/Bus bars or any other places. as per specification No: WGMA/ BW                                               | 138 | 50 | Rupees One Hundred ThirtyEight Paise Fifty Only | Mtr  | 138.50 |  |  |  |
| 61 | 1.00 | Item No.6 (CSR:1-3-4)<br>Supplying & erecting mains with 2x6 sq.mm F.R copper PVC insulated wire laid in provided coduit / trunking/ inside pole/Bus bars or any other places. as per specification No: WGMA/ BW                                               | 228 | 0  | Rupees Two Hundred TwentyEight Only             | Mtr  | 228.00 |  |  |  |
| 62 | 1.00 | Item No.7 (CSR:1-5-5)<br>Supplying and erecting ceiling rose/ batten holder/ slanting holder/ hanging cord switch/ hanging bell push/ pendant holder bakelite base 6A erected on filled polypropylene board or polished double wooden block/ PVC junction box. | 43  | 0  | Rupees FourtyThree Only                         | Each | 43.00  |  |  |  |
| 63 | 1.00 | Item No.8 (CSR:1-5-9)<br>Supplying and erecting flush, shock proof plug socket 6 pin 6A and 16A with switch 16A combined unit erected in recess in 16 gauge M.S sheet box duly painted and connected with earth terminal and leads                             | 142 | 0  | Rupees One Hundred FourtyTwo Only               | Each | 142.00 |  |  |  |
| 64 | 1.00 | Item No.9 (CSR:1-5-15)<br>Supplying 16 amp. 3 pin plug Top bakelite type of 230 V. A.C supply.                                                                                                                                                                 | 75  | 0  | Rupees SeventyFive Only                         | Each | 75.00  |  |  |  |
| 65 | 1.00 | Item No.10 (CSR:1-6-1)<br>Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.                                                                                                | 72  | 0  | Rupees SeventyTwo Only                          | Each | 72.00  |  |  |  |
| 66 | 1.00 | Item No.11 (CSR:1-6-2)<br>Supplying and erecting ISI mark modular type switch 16A duly erected on provided plate and box with wiring connections complete.                                                                                                     | 108 | 0  | Rupees One Hundred Eight Only                   | Each | 108.00 |  |  |  |
| 67 | 1.00 | Item No.12 (CSR:1-6-11)<br>Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring connections complete.                                                                                        | 186 | 0  | Rupees One Hundred EightySix Only               | Each | 186.00 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |    |                                                             |       |         |  |  |  |
|----|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|-------------------------------------------------------------|-------|---------|--|--|--|
| 68 | 1.00 | Item No.13 (CSR:1-6-30)<br>Supplying and erecting PVC surface modular switch box with double mounting plate for 6 module complete duly erected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 252  | 0  | Rupees Two Hundred FiftyTwo Only                            | Each  | 252.00  |  |  |  |
| 69 | 1.00 | Item No.14 (CSR:1-6-31)<br>Supplying and erecting PVC surface modular switch box with double mounting plate for 8 module complete duly erected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 311  | 0  | Rupees Three Hundred Eleven Only                            | Each  | 311.00  |  |  |  |
| 70 | 1.00 | Item No.15 (CSR:1-6-32)<br>Supplying and erecting PVC surface modular switch box with double mounting plate for 12 module complete duly erected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 391  | 0  | Rupees Three Hundred NinetyOne Only                         | Each  | 391.00  |  |  |  |
| 71 | 1.00 | Item No.16 (CSR:1-6-44)<br>Supplying and erecting 6 to 32 A, 10kA, SPMCB suitable to fix in 1 module of modular switch in provided box complete & duly concealed with necessary material and connected                                                                                                                                                                                                                                                                                                                                                                                                                              | 379  | 50 | Rupees Three Hundred SeventyNine Paise Fifty Only           | Each  | 379.50  |  |  |  |
| 72 | 1.00 | Item No.17 (CSR:1-6-45)<br>Supplying and erecting 16 to 32A, 10kA, DPMCB suitable to fix in 2 module of modular switch in provided box complete & duly concealed with necessary material and connected                                                                                                                                                                                                                                                                                                                                                                                                                              | 423  | 0  | Rupees Four Hundred TwentyThree Only                        | Each  | 423.00  |  |  |  |
| 73 | 1.00 | Item No.18 (CSR:1-7-18)<br>Point wiring for light/bell/exhaust fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW                                                                                                                                                                                                                                                                                                                                                                                         | 519  | 0  | Rupees Five Hundred Nineteen Only                           | Point | 519.00  |  |  |  |
| 74 | 1.00 | Item No.19 (CSR:1-7-20)<br>Point wiring for independent plug in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW<br>Note:- 1) In case length of point wiring exceeds 6 meters, add 10% of rate, for every additional length of 1 metre or part thereof.                                                                                                                                                                                                                                                        | 719  | 0  | Rupees Seven Hundred Nineteen Only                          | Point | 719.00  |  |  |  |
| 75 | 1.00 | Item No.20 (CSR:2-1-6)<br>Supplying and erecting LED square / circular Max. 25 W down lighter /Panel Light having pressure die-cast aluminium housing, polystyrene diffuser having system lumens output of Min. 2000 Lumens, min. efficacy of 110 lumen/W, CRI>80, CCT upto 6500K, Beam Angle of 120 deg., max. ripple of 5%, THD<10%, p.f. >0.95, operating range of 120-270V, surge protection of 2.5 kV, Life class of 50,000 Hrs at L70B0 including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete with minimum 2 years warranty as per specification No. FG-IDF/LED. | 2917 | 50 | Rupees Two Thousand Nine Hundred Seventeen Paise Fifty Only | Each  | 2917.50 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |    |                                                            |      |         |  |  |  |
|----|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|------------------------------------------------------------|------|---------|--|--|--|
| 76 | 1.00 | Item No.21 (CSR:2-1-8)<br>Supplying and erecting LED Panel Light (600mm X 600mm) Max. 35 Whaving CRCA powder coated housing, polystyrene diffuser having system lumens output of Min 4200 Lumens, min. efficacy of 120 lumen/W, CRI>80, CCT upto 6500K, Beam Angle of 120 deg., max. ripple of 5%, THD<10%, p.f. >0.95, operating range of 120-270V, surge protection of 2.5 kV, Life class of 50,000 Hrs at L70B50 including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete with minimum 2 yearswarranty as per specification No. FG-IDF/LED. | 3750 | 50 | Rupees Three Thousand Seven Hundred Fifty Paise Fifty Only | Each | 3750.50 |  |  |  |
| 77 | 1.00 | Item No.22 (CSR:2-1-16)<br>Supplying and erecting anodized aluminium corridor / passage / mirror light LED fitting (2 feet) Max. 12W with high transitivity diffuser with min. system lumens output of 1200 lumens, min. efficacy of 100 lumen/W, CRI>80, CCT upto 6000K, Beam Angle of 110 deg., Ripple<5%, THD<10%, p.f. >0.95, operating range of 200-270V, surge protection of 2 kV, Life class of 50,000 Hrs. at L70B50, including driver with end caps on provided PVC Block / wooden board with 3 years warranty.                                                                                 | 455  | 0  | Rupees Four Hundred FiftyFive Only                         | Each | 455.00  |  |  |  |
| 78 | 1.00 | Item No.23 (CSR:2-1-18)<br>Supplying and erecting anodized aluminium corridor / passage / mirror light LED fitting (4 feet) Max. 22W with high transitivity diffuser with min. system lumens output of 1200 lumens, min. efficacy of 100 lumen/W, CRI>80, CCT upto 6000K, Beam Angle of 110 deg., Ripple<5%, THD<10%, p.f. >0.95, operating range of 200-270V, surge protection of 2 kV, Life class of 50,000 Hrs. at L70B50, including driver with end caps on provided PVC Block / wooden board with 3 years warranty.                                                                                 | 998  | 50 | Rupees Nine Hundred NinetyEight Paise Fifty Only           | Each | 998.50  |  |  |  |
| 79 | 1.00 | Item No.24 (CSR:2-2-8)<br>Supplying and erecting electronic type driver for indoor LED 19W - 24W fixtures suitable to operate on 230V A.C. 50 Hz having p.f.>0.95 and THD<10% as per specification No. FG-AS.                                                                                                                                                                                                                                                                                                                                                                                            | 646  | 0  | Rupees Six Hundred FourtySix Only                          | Each | 646.00  |  |  |  |
| 80 | 1.00 | Item No.25 (CSR:2-3-4)<br>Supplying and erecting integrated LED street light fitting 40 to 50W IP65 & IK08 class having single piece pressure die-cast aluminium housing, having system lumens output of Min. 2300 Lumens, min. efficacy of 100 lumen/W, CRI>70, CCT upto 6500K, THD<10%, p.f. >0.95, operating range of 140-270V, inbuilt surge protection of 10 kV, Life class of 50,000 Hrs. at L70B50, including driver complete with 3Years warranty as per specification No FG-ODF/FLS2.                                                                                                           | 4223 | 0  | Rupees Four Thousand Two Hundred TwentyThree Only          | Each | 4223.00 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |   |                                                   |      |         |  |  |  |
|----|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|---------------------------------------------------|------|---------|--|--|--|
| 81 | 1.00 | Item No.26 (CSR:2-3-8)<br>Supplying and erecting integrated LED street light fitting 100-110W IP65 & IK08 class having single piece pressure die-cast aluminium housing, having system lumens output of Min. 2300 Lumens, min. efficacy of 100 lumen/W, CRI>70, CCT upto 6500K, THD<10%, p.f. >0.95, operating range of 140-270V, inbuilt surge protection of 10 kV, Life class of 50,000 Hrs. at L70B50, including driver complete with 3Years warranty as per specification No FG-ODF/FLS2. | 7315 | 0 | Rupees Seven Thousand Three Hundred Fifteen Only  | Each | 7315.00 |  |  |  |
| 82 | 1.00 | Item No.27 (CSR:2-6-4)<br>Supplying and erecting street light Wall bracket made from 40 mm. dia 'B' class G.I. pipe 1.2 m in total length complete as per specification no. FGBKT/ WB.                                                                                                                                                                                                                                                                                                        | 867  | 0 | Rupees Eight Hundred SixtySeven Only              | Each | 867.00  |  |  |  |
| 83 | 1.00 | Item No.28 (CSR:2-6-5)<br>Supplying and erecting Street light bracket for erection of Single fitting made from 40 mm. dia 'B' class G.I. pipe 1.0 m in length along with pole cap of 300 mm length 100 mm dia duly welded as per specification no. FG-BKT/SLB                                                                                                                                                                                                                                 | 1071 | 0 | Rupees One Thousand SeventyOne Only               | Each | 1071.00 |  |  |  |
| 84 | 1.00 | Item No.29 (CSR:2-6-16)<br>Supplying and erecting electronic type Driver for Outdoor LED fittings upto 151W-200W suitable to operate on 230V A.C. 50 Hz. having p.f>0.95 and THD<10% as per specification no. FG-ODF/AS.                                                                                                                                                                                                                                                                      | 2563 | 0 | Rupees Two Thousand Five Hundred SixtyThree Only  | Each | 2563.00 |  |  |  |
| 85 | 1.00 | Item No.30 (CSR:2-7-5)<br>Supplying & erecting 10-12W, 230V integral type LED Lamp suitable for B-22/E-27 base as per specification no. FG-LP.                                                                                                                                                                                                                                                                                                                                                | 266  | 0 | Rupees Two Hundred SixtySix Only                  | Each | 266.00  |  |  |  |
| 86 | 1.00 | Item No.31 (CSR:2-9-3)<br>Supplying and erecting regular/ standard model ceiling fan of 1400mm. Sweep complete erected in position as per specification no. FG-FN/CF                                                                                                                                                                                                                                                                                                                          | 2107 | 0 | Rupees Two Thousand One Hundred Seven Only        | Each | 2107.00 |  |  |  |
| 87 | 1.00 | Item No.32 (CSR:2-9-13)<br>Supplying and erecting exhaust fan medium duty 230 V A.C. 50 cycles 225 mm. 1400 RPM with condenser complete erected in position with necessary materials. Fan motor with moisture proof treatment and 'E' class insulation.                                                                                                                                                                                                                                       | 1701 | 0 | Rupees One Thousand Seven Hundred One Only        | Each | 1701.00 |  |  |  |
| 88 | 1.00 | Item No.33 (CSR:4-8-6)<br>Supplying and erecting programmable digital almanac timer microcontroller based with real time clock to operate on derived switching "ON" and switching "OFF" street light as per daily sunset and sunrise respectively automatically having 4 digit LED continuous time display, relay output 230V / 10A with 10 hrs. battery backup and manual over drive facility capable to drive different capacity contactors timer erected in provided M.S. box.             | 2948 | 0 | Rupees Two Thousand Nine Hundred FourtyEight Only | Each | 2948.00 |  |  |  |

|    |      |                                                                                                                                                                                                                                                                                                                                                                         |      |   |                                                   |           |         |  |  |  |
|----|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|---------------------------------------------------|-----------|---------|--|--|--|
| 89 | 1.00 | Item No.34 (CSR:4-8-7)<br>Providing and fixing high-density polyethylene (HDP) container one piece moulded water tank made out of high density polyethylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all tanks capacity up to 20000 litres.                     | 11   | 0 | Rupees Eleven Only                                | Per Litre | 11.00   |  |  |  |
| 90 | 1.00 | Item No.35 (CSR:5-1-4)<br>Supplying & erecting four pole ON LOAD change over switch, 415V, 100A, open execution having staggered termination, phase barrier, shroud termination and terminal cover along with auxiliary contacts and ready to upgrade with fuse protection kit, rotary handle, operational current category AC23A complying to IS/IEC 60947-3 Part-1/3. | 5027 | 0 | Rupees Five Thousand TwentySeven Only             | Each      | 5027.00 |  |  |  |
| 91 | 1.00 | Item No.36 (CSR:5-3-3)<br>Supplying erecting & marking SPMCB 6A to 32 A B - series in provided distribution board as per specification no.SW - SWR / MCB                                                                                                                                                                                                                | 173  | 0 | Rupees One Hundred SeventyThree Only              | Each      | 173.00  |  |  |  |
| 92 | 1.00 | Item No.37 (CSR:5-3-5)<br>Supplying erecting & marking SPMCB 40A to 63 A B - series in provided distribution board as per specification no.SW - SWR / MCB                                                                                                                                                                                                               | 351  | 0 | Rupees Three Hundred FiftyOne Only                | Each      | 351.00  |  |  |  |
| 93 | 1.00 | Item No.38 (CSR:5-3-7)<br>Supplying, erecting & marking DPMCB 6 A to 32 A, B-series in provided distribution board as per specification no. SW - SWR / MCB                                                                                                                                                                                                              | 510  | 0 | Rupees Five Hundred Ten Only                      | Each      | 510.00  |  |  |  |
| 94 | 1.00 | Item No.39 (CSR:5-3-11)<br>Supplying, erecting & marking TPMCB 40A to 63A in provided distribution board as per specification no. SW-SWR/MCB                                                                                                                                                                                                                            | 992  | 0 | Rupees Nine Hundred NinetyTwo Only                | Each      | 992.00  |  |  |  |
| 95 | 1.00 | Item No.40(CSR:5-3-13)<br>Supplying, erecting & marking FPMCB 40 A to 63 A in provided distribution board as per specification no. SW - SWR / MCB                                                                                                                                                                                                                       | 1329 | 0 | Rupees One Thousand Three Hundred TwentyNine Only | Each      | 1329.00 |  |  |  |
| 96 | 1.00 | Item No.41 (CSR:5-4-1)<br>Supplying and erecting triple pole and neutral distribution board (TPNDB) surface/ flush mounted SP /TP MCBs of 12 ways on iron / GI frame (vertical busbar type) as per specification no. SW-SWR/ MCBDB                                                                                                                                      | 2391 | 0 | Rupees Two Thousand Three Hundred NinetyOne Only  | Each      | 2391.00 |  |  |  |
| 97 | 1.00 | Item No.42 (CSR:5-4-7)<br>Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 2 ways (2 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface / flush mounted, IP 43 Protection on iron / GI frame as per specification no. SW-SWR/MCBDB                                                                  | 818  | 0 | Rupees Eight Hundred Eighteen Only                | Each      | 818.00  |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                          |      |   |                                                  |      |         |  |  |  |
|-----|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--------------------------------------------------|------|---------|--|--|--|
| 98  | 1.00 | Item No.43 (CSR:5-4-8)<br>Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 4 ways (4 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame as per specification no. SW-MCBDB                  | 984  | 0 | Rupees Nine Hundred EightyFour Only              | Each | 984.00  |  |  |  |
| 99  | 1.00 | Item No.44 (CSR:5-4-11)<br>Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 10 ways (10 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface / flush mounted, IP 43 Protection on iron / GI frame as per specification no. SW-SWR/MCBDB                | 1605 | 0 | Rupees One Thousand Six Hundred Five Only        | Each | 1605.00 |  |  |  |
| 100 | 1.00 | Item No.45 (CSR:5-5-1)<br>Providing and erecting 3 Pole MCCB upto 100A, 415V capacity with S.C. rating 25 kA, thermal and magnetic setting with provided leads on iron frame as per specification no. SW-SWR/MCCB.<br>Note:- 1)For use of 4 pole MCCBs in place of 3 pole MCCBs add 20% in rate of 3 pole MCCB.          | 5808 | 0 | Rupees Five Thousand Eight Hundred Eight Only    | Each | 5808.00 |  |  |  |
| 101 | 1.00 | Item No.46 (CSR:5-6-2)<br>Supplying, erecting & commissioning 2 pole RCCB 40A, electromagnetic type with 30/100/300 mA sensitivity with earth leakage trip indication complete as per specification no. SW-RCCB.                                                                                                         | 3490 | 0 | Rupees Three Thousand Four Hundred Ninety Only   | Each | 3490.00 |  |  |  |
| 102 | 1.00 | Item No.47 (CSR:5-10-14)<br>Supplying & erecting HRC fuse cartridge 415V, 200A                                                                                                                                                                                                                                           | 298  | 0 | Rupees Two Hundred NinetyEight Only              | Each | 298.00  |  |  |  |
| 103 | 1.00 | Item No.48 (CSR:5-10-20)<br>Supplying & erecting 415V 100A porcelain base neutral link complete erected in provided MS box complete..                                                                                                                                                                                    | 210  | 0 | Rupees Two Hundred Ten Only                      | Each | 210.00  |  |  |  |
| 104 | 1.00 | Item No.49(CSR:6-1-1)<br>Supplying and erecting metal work in CRCA sheet with fabrication of boxes, panel boards, etc. including cutting, bending, drilling, welding, riveting, treated with anti-rust treatment and duly powder coated or painted with one coat of red lead paint and 2 coats of enamel paint complete. | 261  | 0 | Rupees Two Hundred SixtyOne Only                 | Kg   | 261.00  |  |  |  |
| 105 | 1.00 | Item No.50 (CSR:6-1-14)<br>Supplying and erecting marine plywood 18/19 mm thick fixed to wall or on provided panel board with necessary materials such as screws, wall fasteners, supports, nut bolts etc. complete.<br>2) For Fire retardant plywood increase rate by 25%                                               | 1529 | 0 | Rupees One Thousand Five Hundred TwentyNine Only | Sqmm | 1529.00 |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |   |                                                |      |         |  |  |  |
|-----|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|------------------------------------------------|------|---------|--|--|--|
| 106 | 1.00 | Item No.51 (CSR:6-1-18)<br>Supplying and erecting cupboard for enclosing switchgears or for any other purpose made from selected marine plywood planks 19 mm thick duly varnished/ painted from inside and from outside with brass hinges and locking arrangement with suitable lock with keys in duplicate. Cupboard shall be duly grouted with suitable size of iron work in wall at the bottom. (Size of cupboard shall be specified in the estimate) | 2622 | 0 | Rupees Two Thousand Six Hundred TwentyTwo Only | Sqmm | 2622.00 |  |  |  |
| 107 | 1.00 | Item No.52 (CSR:7-2-8)<br>Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 2 core 2.5 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU                                                                                                                                            | 198  | 0 | Rupees One Hundred NinetyEight Only            | Mtr. | 198.00  |  |  |  |
| 108 | 1.00 | Item No.53 (CSR:7-2-9)<br>Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 2 core 4 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU                                                                                                                                              | 197  | 0 | Rupees One Hundred NinetySeven Only            | Mtr. | 197.00  |  |  |  |
| 109 | 1.00 | Item No.54 (CSR:7-2-31)<br>Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 4 core 4 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU                                                                                                                                             | 440  | 0 | Rupees Four Hundred Fourty Only                | Mtr  | 440.00  |  |  |  |
| 110 | 1.00 | Item No.55 (CSR:7-2-32)<br>Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 4 core 6 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU                                                                                                                                             | 482  | 0 | Rupees Four Hundred EightyTwo Only             | Mtr. | 482.00  |  |  |  |
| 111 | 1.00 | Item No.56 (CSR:7-2-33)<br>Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 4 core 10 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU                                                                                                                                            | 775  | 0 | Rupees Seven Hundred SeventyFive Only          | Mtr. | 775.00  |  |  |  |
| 112 | 1.00 | Item No.57 (CSR:7-6-9)<br>Supplying and laying (including excavation of suitable width & depth up to 90 cm) 50 mm outside dia. double wall corrugated pipes (DWC) of HDPE for enclosing cable below ground/road surface, complete.                                                                                                                                                                                                                       | 204  | 0 | Rupees Two Hundred Four Only                   | Mtr  | 204.00  |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                                                                      |       |   |                                                    |      |          |  |  |  |
|-----|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---|----------------------------------------------------|------|----------|--|--|--|
| 113 | 1.00 | Item No.58 (CSR:7-7-1)<br>Supplying & erecting single compression type brass cable glands for 2 to 4 core 2.5 sq mm /2 to 4 core 4 sq mm /2 core 6 sq mm. for XLPE armoured cable as per specification No. CB-GL                                                                                                                                                                                     | 73    | 0 | Rupees SeventyThree Only                           | Each | 73.00    |  |  |  |
| 114 | 1.00 | Item No.59 (CSR:7-8-10 )<br>Supplying & erecting FRP box of size 300 x 200 x 125 mm, 2.7 mm thick complete on pole/wall as per specification no. CB-SB                                                                                                                                                                                                                                               | 790   | 0 | Rupees Seven Hundred Ninety Only                   | Each | 790.00   |  |  |  |
| 115 | 1.00 | Item No.60 (CSR:7-9-1)<br>Supplying & erecting crimping type copper lugs for cable up to 16 sq. mm. complete as per specification no. CB-CL/CU                                                                                                                                                                                                                                                       | 24    | 0 | Rupees TwentyFour Only                             | Each | 24.00    |  |  |  |
| 116 | 1.00 | Item No.61 (CSR:7-11-8)<br>Providing & erecting Hot dipped galvanized perforated type cable tray manufactured from 16 swg (1.6 mm thick) GI sheet of 300 mm width & 75 mm height complete with necessary coupler plates & hardware in approved manner.                                                                                                                                               | 846   | 0 | Rupees Eight Hundred FourtySix Only                | Mtr  | 846.00   |  |  |  |
| 117 | 1.00 | Item No.62 (CSR:9-1-4 )<br>Providing pipe type earthing with 40mm. dia. G.I. pipe or 20 mm dia. G.I. Rod complete with all materials as per specification no. EAEP                                                                                                                                                                                                                                   | 1537  | 0 | Rupees One Thousand Five Hundred ThirtySeven Only  | Each | 1537.00  |  |  |  |
| 118 | 1.00 | Item No.63 (CSR:9-1-6 )<br>Supplying, installing and testing earthing with copper earth plate size 60 x 60 x 0.315 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover with minimum 25 kg Carbon based environment friendly back fill ground ehancing compound complete with all accesories of copper materials & recording the results as per specification no EA-EP/EF | 15816 | 0 | Rupees Fifteen Thousand Eight Hundred Sixteen Only | Each | 15816.00 |  |  |  |
| 119 | 1.00 | Item No.64 (CSR:9-2-8)<br>Supplying and erecting GI strip of required size used for earthing on wall and/or any other purpose with necessary GI clamps fixed on wall painted with insulating and non-corrosive bond with required joints as per specification no. EA-EP                                                                                                                              | 467   | 0 | Rupees Four Hundred SixtySeven Only                | Kg   | 467.00   |  |  |  |
| 120 | 1.00 | Item No.65 (CSR:12-1-3)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated centrifugal water pump (monoblock), 230 V, single phase, 50 Hz, A.C. supply of 1.125 kW/1.5HP with discharge 198/50 lpm for head of 15/37.5 m & 40 mm suction/32 mm delivery pipe on provided CC foundation as per specification no. WP-CGP                                            | 12555 | 0 | Rupees Twelve Thousand Five Hundred FiftyFive Only | Each | 12555.00 |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                                                                      |       |   |                                                         |      |          |  |  |  |
|-----|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---|---------------------------------------------------------|------|----------|--|--|--|
| 121 | 1.00 | Item No.66 (CSR:12-1-4)<br>Supplying & erecting Minimum three & above star rated Centrifugal water pump (Monoblock), 230V, Single phase 50 cycles A.C. supply of 1.5 kW/2 HP with discharge 600/140 Litres per Minute (LPM) for head of 8/22 m & 50 mm suction/ 50 mm delivery pipe on provided C.C. foundation as per specification No. WP-CGP                                                      | 1432  | 0 | Rupees Fourteen Thousand Three Hundred FourtyTwo Only   | Each | 14342.00 |  |  |  |
| 122 | 1.00 | Item No.67 (CSR:12-1-6)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated centrifugal water pump (monoblock), 415V, three phase, 50 Hz, A.C. supply of 2.25 kW/ 3 HP with discharge 720/165 lpm for head of 12/26 m and 65 mm suction/50 mm delivery pipe on provided CC foundation as per specification no. WP-CGP.                                             | 22474 | 0 | Rupees TwentyTwo Thousand Four Hundred SeventyFour Only | Each | 22474.00 |  |  |  |
| 123 | 1.00 | Item No.68 (CSR:12-1-9 )<br>Supplying & erecting minimum three & above star rated Centrifugal water pump (Monoblock), 415 V, three phase 50 cycles A.C. supply of 3.75 KW/5 HP with discharge 715/200 Litres per Minute (LPM) for head of 17/39 m and 65 mm suction/ 50 mm delivery pipe on provided C.C. foundation as per specification No. WP-CGP                                                 | 27800 | 0 | Rupees TwentySeven Thousand Eight Hundred Only          | Each | 27800.00 |  |  |  |
| 124 | 1.00 | Item No.69 (CSR:12-3-1)<br>Supplying and erecting minimum Three & above star rated submersible pump set suitable for erection on open well of 2.25 KW/3 HP with 415 V 50 c/s. A.C. supply, having delivery head from 27 to 9 m and discharge from 300 to 660 litres. per minute & pipe of Suction 65mm /Delivery 50 mm diameter erected with necessary H type clamps as per specification No. WP-OSP | 27308 | 0 | Rupees TwentySeven Thousand Three Hundred Eight Only    | Each | 27308.00 |  |  |  |
| 125 | 1.00 | Item No.70 (CSR:12-3-2)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated submersible pump set for open well of 3.75 kW/5 HP with 415 V, three phase, 50 Hz, A.C. supply having delivery head from 43 to 21 m and discharge from 120 to 840 lpm & 65 mm suction/50 mm delivery dia. as per specification no. WP-OSP.                                             | 28285 | 0 | Rupees TwentyEight Thousand Two Hundred EightyFive Only | Each | 28285.00 |  |  |  |
| 126 | 1.00 | Item No.71 (CSR:12-3-4)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated submersible pump set suitable for erection on open well of 5.625 kW/7.5 HP with 415 V, three phase, 50 Hz, A.C. supply having delivery head from 57 to 22 m and discharge from 120 to 900 lpm & 75 mm suction/65 mm delivery dia. as per specification no. WP-OSP.                     | 61633 | 0 | Rupees SixtyOne Thousand Six Hundred ThirtyThree Only   | Each | 61633.00 |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |   |                                                          |      |          |  |  |  |
|-----|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---|----------------------------------------------------------|------|----------|--|--|--|
| 127 | 1.00 | Item No.72 (CSR:12-3-5)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated 230 V, single phase, 50 Hz, A.C. supply submersible pump set of 0.75 kW/1HP for erection on open well, pump having delivery head from 34 to 15 m and discharge from 5 to 180 lpm & 32 mm suction/25 mm delivery dia. as per specification no. WP-OSP.                                                                                 | 16218 | 0 | Rupees Sixteen<br>Thousand Two Hundred<br>Eighteen Only  | Each | 16218.00 |  |  |  |
| 128 | 1.00 | Item No.73 (CSR:12-3-6 )<br>Supplying and erecting minimum Three & above star rated 1 phase, 230 V, 50 Hz, submersible pump set of 1.5 KW/2HP suitable for erection on open well, pump having delivery head from 29 to 7 m and discharge from 30 to 600 litres. . per minute & pipe of Suction 50 mm/Delivery 50 mm diameter erected with necessary H type clamps as per specification No. WP-OSP                                                   | 19911 | 0 | Rupees Nineteen<br>Thousand Nine Hundred<br>Eleven Only  | Each | 19911.00 |  |  |  |
| 129 | 1.00 | Item No.74 (CSR:12-3-7)<br>Supplying, erecting, testing and commissioning of minimum three & above star rated 3 phase, 415 V, 50 Hz, submersible pump set of 7.5 kW/10HP suitable for erection on open well, pump having delivery head from 60 to 28 m and discharge from 120 to 840 litres per minute & 65 mm suction/50 mm delivery dia. as per specification no. WP-OSP                                                                          | 65070 | 0 | Rupees SixtyFive<br>Thousand Seventy Only                | Each | 65070.00 |  |  |  |
| 130 | 1.00 | Item No.75 (CSR:12-4-7)<br>Supplying and erecting pump protection relay comprising current sensing phase failure and UV+OV relay with dry run and overload protection suitable for 3 phase pumps.                                                                                                                                                                                                                                                   | 2897  | 0 | Rupees Two Thousand<br>Eight Hundred<br>NinetySeven Only | Each | 2897.00  |  |  |  |
| 131 | 1.00 | Item No76 (CSR:12-4-8)<br>Supplying and erecting flat flexible 3 core 2.5 sq mm PVC sheathed submersible type copper cable suitably clamped at fixed intervals with column pipe assembly complete.                                                                                                                                                                                                                                                  | 141   | 0 | Rupees One Hundred<br>FourtyOne Only                     | Mtr  | 141.00   |  |  |  |
| 132 | 1.00 | Item No.77 (CSR:12-4-9)<br>Supplying and erecting flat flexible 3 core 4 sq mm PVC sheathed submersible type copper cable suitably clamped at fixed intervals with column pipe assembly complete.                                                                                                                                                                                                                                                   | 258   | 0 | Rupees Two Hundred<br>FiftyEight Only                    | Mtr  | 258.00   |  |  |  |
| 133 | 1.00 | Item No.78 (CSR:12-4-17)<br>Supplying, erecting, testing and commissioning of automatic control panel for three phase , 415 V, A.C. supply, submersible/centrifugal pump set upto 7.5 HP consisting of D.O.L. starter having relay range 9-14 A, S.P.P., combined ammeter/voltmeter, phase indicating lamp enclosed in CRCA powder coated vibration proof enclosure with IP54 protection with single phasing, phase reversal, phase imbalance, etc. | 3900  | 0 | Rupees Three Thousand<br>Nine Hundred Only               | Each | 3900.00  |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |   |                                                            |      |          |  |  |  |
|-----|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---|------------------------------------------------------------|------|----------|--|--|--|
| 134 | 1.00 | Item No.79 (CSR:12-4-20)<br>Supplying, erecting, testing and commissioning of automatic control panel for single phase, 230 V, A.C. supply submersible/centrifugal pump set upto 3 HP consisting of D.O.L. starter of suitable relay range, S.P.P., combined ammeter/ voltmeter, phase indicating lamp enclosed in CRCA powder coated vibration proof enclosure with IP54 protection                                                                                                                                                                                                                                                                           | 4342  |   | Rupees Four Thousand<br>Three Hundred<br>FourtyTwo Only    | Each | 4342.00  |  |  |  |
| 135 | 1.00 | Item No.80 (CSR:12-4-22)<br>Supplying, erecting, testing and commissioning of automatic control panel for three phase, 415 V, A.C. supply submersible/ centrifugal pump set upto 20 HP consisting of star delta starter having relay range 28-42 A, S.P.P., combined ammeter/ voltmeter, phase indicating lamp enclosed in CRCA powder coated vibration proof enclosure with IP54 protection with single phasing, phase reversal, phase imbalance, etc .                                                                                                                                                                                                       | 25600 | 0 | Rupees TwentyFive<br>Thousand Six Hundred<br>Only          | Each | 25600.00 |  |  |  |
| 136 | 1.00 | Item No.81 (CSR:12-4-28)<br>Supplying & erecting Float sensor switch for water level controller working on 250V & rated current 8A, with 2 mtr. wire & High quality of wire & plastic body.                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 413   | 0 | Rupees Four Hundred<br>Thirteen Only                       | Each | 413.00   |  |  |  |
| 137 | 1.00 | Item No.82 (CSR:12-5-2)<br>Supplying, erecting, testing and commissioning of dewatering monoblock pump set 415 V, three phase, 50 Hz, A.C. supply of 3.73kW/ 5 HP of 9 to 18 m head with 1125 to 500 lpm discharge, 15.5mm solid handling capacity, nonclogging minimised abrasive wear, large impeller clearance & maintenance free pump set with waterproof cable duly sealed with epoxy material built in protection to prevent the motor from burn out due to abnormal operation, specially designed high efficiency motor with F class insulation & the pump mechanically sealed in the oil chamber,. etc. complete as per specification no. DWP- SMP.    | 57330 | 0 | Rupees FiftySeven<br>Thousand Three<br>Hundred Thirty Only | Each | 57330.00 |  |  |  |
| 138 | 1.00 | Item No.83 (CSR:12-5-3)<br>Supplying, erecting, testing and commissioning of dewatering monoblock pump set 415 V, three phase, 50 Hz, A.C. supply of 5.5kW/ 7.5 HP, of 21 to 36 m head with 910 to 190 lpm discharge, 14.5 mm Solid handling capacity, nonclogging minimised abrasive wear, large impeller clearance & maintenance free pump set with waterproof cable duly sealed with epoxy material built in protection to prevent the motor from burn out due to abnormal operation. specially designed high efficiency motor with F class insulation & the pump mechanically sealed in the oil chamber,. etc. complete as per specification no. DWP- SMP. | 92802 | 0 | Rupees NinetyTwo<br>Thousand Eight Hundred<br>Two Only     | Each | 92802.00 |  |  |  |

|     |      |                                                                                                                                                                                                                   |      |   |                                                  |      |         |  |  |  |
|-----|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|--------------------------------------------------|------|---------|--|--|--|
| 139 | 1.00 | Item No.84(CSR:12-7-6)<br>Dismantling the existing submersible pump with GI pipeline upto 10 m depth. (For additional depth of each 3 m or part thereof add Rs. 50/- per 3 m, in the rates)                       | 2958 | 0 | Rupees Two Thousand Nine Hundred FiftyEight Only | Each | 2958.00 |  |  |  |
| 140 | 1.00 | Item No.85 (CSR:16-1-2)<br>Making trench in Hard murum/Tar road having 0.75m depth and minimum 0.3m width for laying provided cables up to voltage level 1.1kV cable complete as per specification no. CW-EXN-CTR | 219  | 0 | Rupees Two Hundred Nineteen Only                 | Mtr  | 219.00  |  |  |  |
| 141 | 1.00 | Item No.86 (CSR:16-3-5)<br>Making cement concrete foundation in 1:2:4 cement concrete with foundation bolts and nuts complete. (cost of wooden box is included) (for pumps).                                      | 5011 | 0 | Rupees Five Thousand Eleven Only                 | Each | 5011.00 |  |  |  |
| 142 | 1.00 | Item No.87 (CSR:16-5-3)<br>Supplying and erecting GI pipe 25mm dia. 'B' class at position with accessories complete as per specification no. CW-PLB/GP.                                                           | 327  | 0 | Rupees Three Hundred TwentySeven Only            | Mtr  | 327.00  |  |  |  |
| 143 | 1.00 | Item No.88 (CSR:16-5-11 )<br>Supplying and erecting ISI mark G.I. pipe 40 mm dia. 'C' class at position with accessories as per specification no. CW-PLB/GP                                                       | 461  | 0 | Rupees Four Hundred SixtyOne Only                | Mtr  | 461.00  |  |  |  |
| 144 | 1.00 | Item No.89 (CSR:16-5-12)<br>Supplying and erecting ISI mark G.I. pipe 50 mm dia. 'C' class at position with accessories as per specification no. CW-PLB/GP                                                        | 680  | 0 | Rupees Six Hundred Eighty Only                   | Mtr  | 680.00  |  |  |  |
| 145 | 1.00 | Item No.90 (CSR:16-5-17)<br>Supplying and erecting high density polythene pipe ISI mark 40 mm dia. suitable for pressure of 6 kg/cm2 connected to jet/submersible pump with required material complete.           | 100  | 0 | Rupees One Hundred Only                          | Mtr  | 100.00  |  |  |  |
| 146 | 1.00 | Item No.91 (CSR:16-5-18)<br>Supplying and erecting high density polythene pipe ISI mark 50 mm. dia. suitable for pressure of 6 kg. / cm2 connected to jet/submersible pump with required material complete        | 135  | 0 | Rupees One Hundred ThirtyFive Only               | Mtr  | 135.00  |  |  |  |
| 147 | 1.00 | Item No.92 (CSR:16-6-3)<br>Supplying and erecting 50 mm dia. Gun metal foot valve at position with necessary materials.                                                                                           | 1154 | 0 | Rupees One Thousand One Hundred FiftyFour Only   | Each | 1154.00 |  |  |  |
| 148 | 1.00 | Item No.93 (CSR:16-6-13)<br>Supplying & Erecting 25 mm gun metal sluice valve at position with necessary materials.                                                                                               | 903  | 0 | Rupees Nine Hundred Three Only                   | Each | 903.00  |  |  |  |
| 149 | 1.00 | Item No.94 (CSR:16-6-19)<br>Supplying and erecting non return valve 25 mm dia in position made of gun metal complete.                                                                                             | 556  | 0 | Rupees Five Hundred FiftySix Only                | Each | 556.00  |  |  |  |
| 150 | 1.00 | Item No.95 (CSR:16-6-27)<br>Supplying and erecting C.I. flange 50mm dia with necessary nuts bolts and washers with rubber seal in position.                                                                       | 209  | 0 | Rupees Two Hundred Nine Only                     | Each | 209.00  |  |  |  |

|     |      |                                                                                                                                                                                                                                                                                                                                                      |      |   |                                                    |      |         |  |  |  |
|-----|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---|----------------------------------------------------|------|---------|--|--|--|
| 151 | 1.00 | Item No.96 (CSR:18-1-3)<br>Rewinding motor of the 1200/1400 mm ceiling fan and over hauling including minor repairs lubricating of ball bearings & bush bearing, and replacing condenser, screws etc. Testing of fan for original speed and consumption with guarantee for one year.                                                                 | 552  | 0 | Rupees Five Hundred FiftyTwo Only                  | Each | 552.00  |  |  |  |
| 152 | 1.00 | Item No.97 (CSR:18-1-9)<br>Rewinding of electric motor above 1 HP and upto 2 HP, three phase upto 1400 RPM with copper wire, overhauling with minor repairs, lubricating of ball bearings & bush bearing, and replacing screws etc. testing for the original speed and no load consumption with guarantee for one year                               | 1899 | 0 | Rupees One Thousand Eight Hundred NinetyNine Only  | Each | 1899.00 |  |  |  |
| 153 | 1.00 | Item No.98 (CSR:18-1-10)<br>Rewinding of electric motor above 2 HP and upto 3 HP, three phase upto 1400 RPM with copper wire, overhauling with minor repairs, lubricating of ball bearings & bush bearing, and replacing screws etc. testing for the original speed and no load consumption with guarantee for one year                              | 2155 | 0 | Rupees Two Thousand One Hundred FiftyFive Only     | Each | 2155.00 |  |  |  |
| 154 | 1.00 | Item No.99 (CSR:18-1-11)<br>Rewinding of electric motor above 3 HP and upto 5 HP, three phase upto 1400 RPM with copper wire, overhauling with minor repairs, lubricating of ball bearings & bush bearing, and replacing screws etc. testing for the original speed and no load consumption with guarantee for one year                              | 3674 | 0 | Rupees Three Thousand Six Hundred SeventyFour Only | HP   | 3674.00 |  |  |  |
| 155 | 1.00 | Item No.100 (CSR:18-1-19)<br>Rewinding of submersible pump motor in borewell of all types and makes upto and including 5 HP with coated copper wires & overhauling with minor repairs, lubricating of ball bearings & bush bearing, and replacing screws etc. testing for the original speed, H.P. and no load consumption & guarantee for one year. | 1850 | 0 | Rupees One Thousand Eight Hundred Fifty Only       | HP   | 1850.00 |  |  |  |
| 156 | 1.00 | Item No.101 (CSR:18-1-20)<br>Rewinding of submersible pump motor in borewell of all types and makes above 5 H.P. upto 25 HP with coated copper wires & overhauling with minor repairs, lubricating of ball bearings & bush bearing, and replacing screws etc. testing for the original speed, H.P. and no load consumption & guarantee for one year. | 2067 | 0 | Rupees Two Thousand SixtySeven Only                | HP   | 2067.00 |  |  |  |
| 157 | 1.00 | Item No.102 (CSR:18-3-3)<br>Supplying and erecting No-Volt-Coil for motor having DOL starters upto 7.5 H.P.                                                                                                                                                                                                                                          | 316  | 0 | Rupees Three Hundred Sixteen Only                  | Each | 316.00  |  |  |  |
| 158 | 1.00 | Item No.103 (CSR:18-3-4)<br>Supplying and replacing no-volt-coil for motor having DOL starters from 7.5 HP to 10 HP.                                                                                                                                                                                                                                 | 674  | 0 | Rupees Six Hundred SeventyFour Only                | Each | 674.00  |  |  |  |
| 159 | 1.00 | Item No.104 (CSR:18-3-12)<br>Supplying and replacing thermal overload relay for motor starter suitable for up to 15 HP.                                                                                                                                                                                                                              | 1498 | 0 | Rupees One Thousand Four Hundred NinetyEight Only  | Each | 1498.00 |  |  |  |

|     |            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |    |                                                                          |      |         |  |  |  |
|-----|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|--------------------------------------------------------------------------|------|---------|--|--|--|
| 160 | 1.00       | Item No.105 (CSR:18-3-19)<br>Supplying & replacing timer for star-delta motor starter up to 12.5 HP.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 671  | 0  | Rupees Six Hundred<br>SeventyOne Only                                    | Each | 671.00  |  |  |  |
| 161 | 1.00       | Item No.106 (CSR:18-3-22)<br>Supplying & replacing contactor for DOL motor starter from 7.5 HP to 10 HP.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 1323 | 0  | Rupees One Thousand<br>Three Hundred<br>TwentyThree Only                 | Each | 1323.00 |  |  |  |
| 162 | 1.00       | Item No.107 (CSR:18-3-23)<br>Supplying & replacing contactor for star-delta motor starter from 12.5 HP to 15 HP..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 1833 | 0  | Rupees One Thousand<br>Eight Hundred<br>ThirtyThree Only                 | Each | 1833.00 |  |  |  |
| 163 | ANNEXURE C |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |    |                                                                          |      |         |  |  |  |
| 164 | 1.00       | Item no.108<br>maintenance work of passanger lift upto 7th floor storey building<br>Overhauling of Gearbox by opening the gear box, cleaning the oil path with oil adjusting the Thrust bearing, & bush with packings etc. and refilling with the fresh oil of requisite viscosity and sufficient quantity, complete with re-erection as original with necessary alignment & testing. in MBMC area (comprehensive)<br>job includes visit as & when complain arised( Rate per Month per lift)<br>Job includes 1) Monthly servicing<br>2) on call repair<br>3) replacement of all spares within 24 hours<br>4) sending standby manpower for VIP movement.<br>The job include sheet metal work and plastic material with Electrical Parts<br>5) Providing Monthly Service report to Engineer Incharge<br>6) Providing Brake Pad and Shoes at Lift Liners<br>7) All Type Limit Switches<br>8) Providing Cop Panel<br>9) Providing Monthly Door Alignment and servicing<br>10) Provide Door Bearing and Belt material<br>11) Providing All Software Programming work at Panel<br>12) Providing essential Rope/Cable at Required Site<br>13) Shaft Wiring,call Button Inside And OutSide<br>14) Lift VFD Drive Work Should be Provided Same Complaint day(MR) | 9823 | 50 | Rupees Nine Thousand<br>Eight Hundred<br>TwentyThree Paise Fifty<br>Only | NOS  | 9823.50 |  |  |  |

|     |             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |   |                                                         |           |          |  |  |  |
|-----|-------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---|---------------------------------------------------------|-----------|----------|--|--|--|
| 165 | 1.00        | Item no.109<br>maintenance work of passanger lift upto 23th floor storey building<br>Overhauling of Gearbox by opening the gear box, cleaning the oil path with oil adjusting the Thrust bearing, & bush with packings etc. and refilling with the fresh oil of requisite viscosity and sufficient quantity, complete with re-erection as original with necessary alignment & testing. in MBMC area (comprehensive) job includes visit as & when complain arised( Rate per Month per lift)<br>Job includes 1) Monthly servicing<br>2) on call repair<br>3) replacement of all spares within 24 hours<br>4) sending standby manpower for VIP movement.<br>The job include sheet metal work and plastic material with Electrical Parts<br>5) Providing Monthly Service report to Engineer Incharge<br>6) Providing Brake Pad and Shoes at Lift Liners<br>7) All Type Limit Switches<br>8) Providing Cop Panel<br>9) Providing Monthly Door Alignment and servicing<br>10) Provide Door Bearing and Belt material<br>11) Providing All Software Programming work at Panel<br>12) Providing essential Rope/Cable at Required Site<br>13) Shaft Wiring,call Button Inside And OutSide<br>14) Lift VFD Drive Work Should be Provided Same Complaint day(MR) | 10871 | 0 | Rupees Ten Thousand<br>Eight Hundred<br>SeventyOne Only | NOS       | 10871.00 |  |  |  |
| 166 | ANNEXURE -E |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |   |                                                         |           |          |  |  |  |
| 167 | 1.00        | ITEM NO. 1<br>Providing Housekeeper of approved agency for cleaning of the given premises and will be responsible for the cleanliness of the premises.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 989   | 0 | Rupees Nine Hundred<br>EightyNine Only                  | Per Shift | 989.00   |  |  |  |
| 168 | 1.00        | ITEM NO. 2<br>Providing Valve man of approved agency for distributing of water supply to the building.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 989   | 0 | Rupees Nine Hundred<br>EightyNine Only                  | Per Shift | 989.00   |  |  |  |

Contractor /Agency

No.of Correction :

Executive Engineer  
Mira-Bhaindar Municipal Corporation