

MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

Name of Work: Providing and Fixing Benches for Womens in Ward No.21 at Miraroad (E) in MBMC Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	11.00	ITEM NO.1 Providing and Fixing VVIP Benches Ground Space: 1.50 Meter x 0.6 Meter Safe Play Area: 2.30 x 2.00 Meter Structure: This bench is an Attractive Kind of Bench for using it in Gardens or at Swimming Pools. This Bench Shall Comfortably Accommodate 3 Adults on it. The stand consist of Cast Iron Structure. Bench backrest support is made of 50 x 3 mm MS Flat. The seating strips is made of Fiber Reinforced Plastic (FRP) material. Nut Bolts: All Nut Bolts G.I. material.Powder Coating: The Equipment shall first be coated with using Akzonobel / Berger / Prime make or its equivalent primer powder coating of at least Thirty microns, followed by Polyester Powder Coating of at least 30 to 50 microns thickness using Akzonobel / Berger / Prime make or equivalent. Powder coating colour is TGTC & Lead free & passes the One Thousand-hour salt spray test & MEK solvent resistance rub test – ASTM D5402	37911	0	Rupees Thrity Seven Thousand Nine Hundred Eleven Only	No.	417021.00			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	0.83	ITEM NO. 2 Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite /gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) SSR 24.08/ 218	8029	76	Rupees Eight Thousand Twenty Nine & Seventy Six Only	Cu.Mt.	6702.84			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation