

MIRA-BHAIKAR MUNICIPAL CORPORATION
SCHEDULE 'B'

Name of Work :- Proposed Construction of Wall at Nalla Beside Bappa Sitaram Temple in Ward No.21 at Miraroad (E.) in MBMC Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	6.30	ITEM NO.1 Providing and laying Cast in situ/Ready Mix cement concrete in M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compactionand roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR 25.52/181	14360	66	Rupees Fourteen Thousand Three Hundred Sixty Paise SixtySix Only	CMT	90472.16			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	0.95	ITEM NO.2 Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. SSR 26.33/188	94188	15	Rupees NinetyFour Thousand One Hundred EightyEight Paise Fifteen Only	MT	89007.80			As Above
3	25.20	ITEM NO.3 Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering and scaffolding Complete. SSR 27.05/197	10027	16	Rupees Ten Thousand TwentySeven Paise Sixteen Only	Cu.Mt.	252684.43			As Above

4	189.00	ITEM NO.4 Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. SSR 32.11/209	700	64	Rupees Seven Hundred Paise SixtyFour Only	Sq.Mt	132420.96			As Above
5	189.00	ITEM NO.5 Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For Item No. 15 to 18 prior approval of Superintending Engineer will be necessary SSR 35.26/225	309	75	Rupees Three Hundred Nine Paise SeventyFive Only	Sq.Mt	58542.75			As Above
6	189.00	ITEM NO.6 Providing and applying priming coat on concrete / masonry /Asbestos Cement plastered surfaces including scaffolding if necessary,preparing the surface by thoroughly cleaning oil,grease,dirt and other foreign matter and sand papering as required etc.complete. SSR 35.21/225	37	80	Rupees ThirtySeven Paise Eighty Only	Sq.Mt.	7144.20			As Above
7	0.52	ITEM NO.7 Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anti corrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete. SSR 23.04/ 214	125431	95	Rupees One Lakh TwentyFive Thousand Four Hundred ThirtyOne Paise NinetyFive Only	MT	64949.92			As Above

8	4.00	ITEM NO.8 Providing and Fixing VVIP Benches Ground Space: 1.50 Meter x 0.6 Meter Safe Play Area: 2.30 x 2.00 Meter Structure: This bench is an Attractive Kind of Bench for using it in Gardens or at Swimming Pools. This Bench Shall Comfortably Accommodate 3 Adults on it. The stand consist of Cast Iron Structure. Bench backrest support is made of 50 x 3 mm MS Flat. The seating strips is made of Fiber Reinforced Plastic (FRP) material. Nut Bolts: All Nut Bolts G.I. material.Powder Coating: The Equipment shall first be coated with using Akzonobel / Berger / Prime make or its equivalent primer powder coating of at least Thirty microns, followed by Polyester Powder Coating of at least 30 to 50 microns thickness using Akzonobel / Berger / Prime make or equivalent. Powder coating colour is TGTC & Lead free & passes the One Thousand-hour salt spray test & MEK solvent resistance rub test – ASTM D5402	37911	0	Rupees ThirtySeven Thousand Nine Hundred Eleven Only	No.	151644.00			As Above
9		ITEM NO.9 Material testing								As Above
	1.00	Compressive Strength OF C.C. Cube (Set of 3 cubes) Page No.584	690	0	Rupees Six Hundred Ninety Only	No.	690.00			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation