

**MIRA-BHANDAR MUNICIPAL CORPORATION
SCHEDULE 'B'**

Name of Work :- Providing & fixing water filter and construction Of waiting room at deputy registrar, cooperative societies at bhaindar (w) in M.B.M.C. Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	#REF!	ITEM NO.1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum- including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc.complete. (Lift fUpto 1.5 m.) SSR 21.02	164	85	Rupees One Hundred Sixty Four Paise Eighty Five Only	CMT	38442.60			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	#REF!	ITEM NO.2 Trasportation up to 3.00 km lead SSR in Statement C-1	369	63	Rupees Three Hundred Sixty Nine Paise Sixty Three Only	SMT	11072.25			As Above
3	#REF!	ITEM NO.3 Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soiling 15 cm to 20 cm thick including hand packing and compacting complete. SSR 21.38	2435	9	Rupees Two Thousand Four Hundred Thirty Five Paise Nine Only	SMT	23885.66			As Above
<p style="text-align: right;">Executive Engineer</p> <p style="text-align: right;">Mira-</p> <p style="text-align: right;">Bhaindar Municipal Corporation</p> <p>Contractor /Agency No.of Correction :</p>										

4	#REF!	ITEM NO.4 Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and oneycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and neycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) SSR 24.08	6156	34	Rupees Six Thousand One Hundred Fifty Six Paise Thirty Four Only	SMT	21912.66			As Above
5	#REF!	ITEM NO. 5 Filling in plinth and floors with contractors soil sand or murum in 15 cm to 20cm, layers including watering and compaction complete. SSR 21.37	914	49	Rupees Nine Hundred Fourteen Paise Fourty Nine Only					As Above
6	#REF!	ITEM NO. 6 Providing and laying in situ cement concrete of specified grade of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, formwork, cover blocks compaction and curing etc SSR 25.13	6767	72	Rupees Six Thousand Seven Hundred Sixty Seven Paise SeventyTwo Only					As Above

	Executive Engineer		Mira-
Contractor /Agency	No.of Correction :	Bhaindar Municipal Corporation	

7	#REF!	ITEM NO. 7 Providing and casting in situ cement concrete specified of trap/ granite / quartzite/ gneiss metal for R.C.C.Column as per detailed designs and drawings including plywood/steel centering, formwork, cover blocks compacting and roughening the surface if special finish is to be provided and curing complete.(Excluding reinforcement). Without SCADA with concrete mixer with hopper	12243	59	Rupees Twelve Thousand Two Hundred FourtyThree Paise Fifty Nine Only					As Above
8	#REF!	ITEM NO.8 Providing and casting in situ cement concrete specified of trap/ granite / quartzite/ gneiss metal for R.C.C. beam as per detailed designs and drawings including plywood/steel centering, formwork, cover blocks compacting and roughening the surface if special finish is to be provided and curing complete.(Excluding reinforcement) hout SCADA with concrete mixer with hopper SSR 25.52	10917	7	Rupees Ten Thousand Nine Hundred Seventeen Paise Seven Only					As Above
9	#REF!	ITEM NO.9 Providing and casting in situ cement concrete specified of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings canopy as per detailed designs and drawings including plywood/steel centering, formwork, cover blocks compacting and roughening the surface if special finish is to be provided and curing complete.(Excluding reinforcement). Without SCADA with concrete mixer with hopper SSR 25.72	13020	36	Rupees Thirteen Thousand Twenty Paise Thirty Six Only					As Above

	Executive Engineer		Mira-
Contractor /Agency	No.of Correction :	Bhaindar Municipal Corporation	

10	#REF!	ITEM NO. 10 Providing and fixing in position H.Y.S.D. FE 415/500 bar reinforcement of of TATA TISCON /SAILI /JSW /ESSAR or equivalent make (condirming to IS code) of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required including cover block etc. complete. SSR 26.33	65710	5	Rupees Sixty Five Thousand Seven Hundred Ten Paise Five Only					As Above
11	#REF!	ITEM NO. 11 Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting complete, SSR 23.04	92131	20	Rupees Ninety Two Thousand One Hundred Thirty One Paise Twenty Only					As Above
12	#REF!	ITEM NO.12 Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering and scaffolding Complete. SSR 27.05	7101	58	Rupees Seven Thousand One Hundred One Paise Fifty Eight Only					As Above
13	#REF!	ITEM NO.13 Providing internal cement plaster 12mm thick in single coat in cement mortar To concrete or brick surfaces, in all positions including scaffolding and curing complete. SSR 32.04	253	68	Rupees Two Hundred Fifty Three Paise Sixty Eight Only					As Above

Executive Engineer

Mira-

Contractor /Agency

No.of Correction :

Bhaindar Municipal Corporation

14	#REF!	ITEM NO.14 Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. SSR 32.11	730	52	Rupees Seven Hundred Thirty Paise Fifty Two Only					As Above
	#REF!	ITEM NO.15 Providing and fixing granite stone telephone black / Amba White /Cadburybrown / RBI red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/window box frame etc. On C.M. 1:6 including filling joints with polymer base filler nosing the sharp edges wherever necessary,curing, etc. complete. SSR 33.34	3833	70	Rupees Three Thousand Eight Hundred Thirty Three Paise Seventy Only					As Above
	#REF!	ITEM NO.16 Providing and laying Semipolished Kota stone flooring over 20mm (average) thick and required width in plain/ diamond pattern on bed of 1:6 Cement mortar including cement float, filling joints with neat cement slurry with pigment to match the shade curing, polishing and cleaning complete. (WithoutPolished) SSR 33.06	1153	5	Rupees One Thousand One Hundred Fifty Three Paise Five Only					As Above
	#REF!	ITEM NO.17 Providing and fixing Single leaf shutter of 35 mm thick, for solid core flush door, decorative type of exterior grade as per detailed drawings or as approved Laminates (Formica) on both faces venetians, all necessary beads, moulding and lipping, brass oxidized / aluminum with power coating fixture & fastenings _____ chromium plated handles on both sides and finishing etc. complete. (without frame) SSR 39.04	8219	40	Rupees Eight Thousand Two Hundred Nineteen Paise Fourty Only					As Above

Executive Engineer

Mira-

Contractor /Agency

No.of Correction :

Bhaindar Municipal Corporation

	#REF!	<p>ITEM NO.18 Providing & laying water proofing treatment of 112 mm average thickness consisting of 12 mm thick layer in cement mortar 1:3 with water proofing compound at the rate of one kilograme per bag of cement as base, constructing & laying brick bat coba in cement mortar 1:5 with water proofing compound at the rate of one kilograme per bag and having average thickness of 80 mm and finishing with 20 mm cement plaster layer in cement mortar 1:3 with approved water proofing compound at the rate 1 kilograme percement bag including all lead, lifts & laid to proper slope to drain off water entirely including watta at the junction of parapet and work up to a height of 30 cm. or as directed and including finishing the top layer of water proofing treatment with false marking of 30 x30 cm. or as directed and covering the whole treatment with 7 years guarantee on requisite stamp paper etc. complete SSR 31.04</p>	1093	73	<p>Rupees One Thousand Ninety Three Paise Seventy Three Only</p>					
	#REF!	<p>ITEM NO.19 Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window JINDAL/ HINDALCO/ OEL OR ANY OTHER approved manufacturer confirming to IS specification of two tracks with rectangular pipe 63 x 38.10 x 1.22 mm at weight 0.650 kg/Rmt. and window frame bottom track section 61.85 x 31.75 x 1.20 mm at weight 0.695 kg/Rmt. Top and side track section 61.85 x 31.75 x 1.20 mm at weight 0.417 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.25 mm at weight 0.469 kg/Rmt. And handle section 52 x 18 x 1.13 mm at weight 0.488 kg/Rmt. and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain/ Colour glass with...all required screws and nuts etc. complete. SSR 39.37</p>	5954	55	<p>Rupees Five Thousand Nine Hundred Fifty Four Paise Fifty Five Only</p>					

Executive Engineer										
Mira-										
Bhaindar Municipal Corporation										
Contractor /Agency		No.of Correction :								
#REF!	ITEM NO.20 Providing and applying two coats of Appex Ultima exterior paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary , and watering the surface for two days complete Spec. No.: As directed by Engineer in charge. SSR 35.26	223	65	Rupees Two Hundred Twenty Three Paise Sixty Five Only						
#REF!	ITEM NO.21 Providing and Fixing MBMC Colour Logo 12 mm thick in Acrylic Sheet, 0.90m Height including Scaffolding etc. Complete. Directed by Engineer incharge on Entrance Gate (Market Rate)	26500	0	Rupees Twenty Six Thousand Five Hundred Only						
#REF!	ITEM NO.22 Providing and fixing 12mm Thick Acrylic Cutletters including all Fitting Scaffolding etc. Complete. Rate Per inch (Market rate)	195	0	Rupees One Hundred Ninety Five Only						
Executive Engineer										
Mira-										
Bhaindar Municipal Corporation										
Contractor /Agency		No.of Correction :								