

MIRA-BHANDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

Name of Work :- Proposed Development of Senior Citizen at Reservation No. 100 in ward No. 08 at Bhaindar(W) in MBMC area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	166.90	ITEM NO. 1 Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. Complete SSR NO. 46.19	47	25	Rupees Forty Seven & Twenty Five Paise Only	smt	7886.24			As per Instruction given by Executive Engineer/ Site Engineer during execution of work
2	18.94	ITEM NO. 2 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting with Vibratory roller. to the required density. By Mechanical Means - Grading I (Using Screening Type A (13.2) mm Aggregate) SSR NO.3.18	4118	0	Rupees Four Thousand One hundred Eighteen Only	CMT	78013.25			As Above
3	18.94	ITEM NO. 3 Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR NO.24.08	8029	76	Rupees Eight Thousand Twenty Nine & Seventy Six Paise Only	CMT	152119.39			As Above

4	0.20	ITEM NO.04 Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete. SSR 23.04 / 129	125431	95	Rupees One Lakh Twenty Five Thousand Four Hundred Thirty One & Ninety Five Paise Only	MT	25086.39		As Above
5	392.50	ITEM NO. 05 Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. SSR NO. 33.06 / 213	1329	14	Rupees One Thousand Three Hundred Twenty nine & fourteen Paise Only	SMT	521693.43		As Above
6	402.50	ITEM NO.06 Providing and fixing plain zinc sheeting of 0.80 mm thick (22 B.W.G.) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt galvanised iron screws and bolts, lead and bitumen washers etc. complete.(Weight of 6.8 kg/sq.m.). SSR NO. 38.05 / 233	1195	95	Rupees One Thousand One Hundred Ninety Five & Ninety Five Paise Only	SMT	481369.88		As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation