

MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

NAME OF WORK: Providing & Laying Of Paver Blocks in open space At Khodiyar Punj Co.operative Housing Society Ltd. Building, ward no. 15, miraroad (E) in MBMC area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	62.98	ITEM NO. 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR NO.21.02 / 153	217	35	Rupees Two Hundred Seventeen Paise ThirtyFive Only	CMT	13688.75			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	62.98	ITEM NO.2 TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m. SSR Statement C-1 (Page 560)	468	37	Rupees Four Hundred SixtyEight Paise ThirtySeven Only	CMT	29498.04			As Above
3	419.87	ITEM NO.3 Providing and fixing heavy duty inter locking concrete Gray paving blocks of 80 mm thickness of having a strength of 300 kg/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete. SSR NO. 33.50 / 218	1107	98	Rupees One Thousand One Hundred Seven Paise NinetyEight Only	SMT	465205.35			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation