

MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

NAME OF WORK: Providing and Fixing of Kota Tiles at Jya malhar chawl-4,vinayak chawl,savitribai fule w.so., shri wellfare so., Gagangiri, minakshi nagar NH No. 08, ward no. 14 in MBMC area.

Item No	Quantity as per Sanctioned Estimate	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	135.05	ITEM NO. 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR NO.21.02 / 153	217	35	Rupees Two Hundred Seventeen Paise ThirtyFive Only	MT	29352.68			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	135.05	ITEM NO.2 TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m. SSR Statement C-1 (Page 560)	468	37	Rupees Four Hundred SixtyEight Paise ThirtySeven Only		63252.43			As Above
3	39.72	ITEM NO. 3 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting with vibratory roller to the required density. By Mechanical Means - Grading II (Using Screening Type B (11.2 mm) Aggregate) SSR NO. 3.20/29ITEM NO. 3 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting with vibratory roller to the required density. By Mechanical Means - Grading II (Using Screening Type B (11.2 mm) Aggregate) SSR NO. 3.20/29	4041	54	Rupees Four Thousand FourtyOne Paise FiftyFour Only		160529.97			As Above

4	59.58	ITEM NO. 4 Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR 24.08 / 176	8029	76	Rupees Eight Thousand TwentyNine Paise SeventySix Only		478413.10			As Above
5	397.20	ITEM NO.5 Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. SSR NO.33.06 / 213	1329	14	Rupees One Thousand Three Hundred TwentyNine Paise Fourteen Only		527934.41			As Above
6	47.66	ITEM NO 6 Royalty	216	18	Rupees Two Hundred Sixteen Paise Eighteen Only		1259482.59			As Above
7	1.00	ITEM NO 7 Material testing	1000	0	Rupees One Thousand Only	SMT	226706.87			As Above

Executive Engineer

Mira-Bhaindar Municipal Corporation

Contractor /Agency

No.of Correction :