

MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

NAME OF WORK : - Providing and fixing of fiber Railing on Gutter Infront of Plaza Vihar co.opp. Ho. Society, ward no.17, Miraroad (E) in MBMC Area.

Item No	Quantity as per Sanctioned Estimate	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	44.54	ITEM NO. 01 Providing & fixing of 1200mm high Glass Fibre Reinforced Composite railing for footpath made of 80x80x8mm inverted profile for fencing column, 50x50x6mm profiles slotted as horizontal members, 25x15mm rods for vertical members, SMC moulded square ring & cap including cover ring for 50x50mm tube. The column shall be fixed on M.S Base plate with 2 coats of red oxide and the same shall be rested on 100mm PCC in 400x400x500mm deep pit. 60 micron thk polyurethane paint. All the components should have fibreglass	28542	0	Rupees Twenty Eight Thousand Five Hundred Fourty Two Only	RMT	1271146.51			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation