MIRA-BHAINDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

NAME OF WORK: Proposed Construction of gutter Slab & stamping in front of City Union bank,silver park road, word no.17, Miraroad (E) in MBMC Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	59.00	ITEM NO. 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR NO.21.02 / 153	217	35	Rupees Two Hundred Seventeen Paise ThirtyFive Only	CMT	12823.74			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	59.00	ITEM NO.2 TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m. SSR Statement C-1 (Page 560)	468	37	Rupees Four Hundred SixtyEight Paise ThirtySeven Only	CMT	27634.02			As Above
3	5.65	ITEM NO. 3 Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	16174	61	Rupees Sixteen Thousand One Hundred SeventyFour Paise SixtyOne Only	CMT	91448.01			As Above

4	0.68	ITEM NO. 4 Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. SSR 26.33/188	94188	15	Rupees NinetyFour Thousand One Hundred EightyEight Paise Fifteen Only	MT	63902.52			As Above
5	0.35	ITEM NO. 5 Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete.	125431	95	Rupees One Lakh TwentyFive Thousand Four Hundred ThirtyOne Paise NinetyFive Only	MT	43755.68			As Above

6	49.17	ITEM NO.6 Stamp Concrete of 100mm Thickness - Providing and Laying in-situ M30 Grade unreinforced plain cement stamp concrete of 100mm thickness pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate (natural sand / VSI grade finely washed crushed sand) Confirming to IS 383, as per mixed in a batching and mixing plant / non tilting mixer and weigh batcher as per approved mix design, admixtures, transporting to site in nagpur city with lead upto 20KM (on Inner Ring Road from Avasti nagar to wadi), spreading, laying with approved make pover, compacted and finished in a continous operation, finishing to lines and grades Also Providing, Placing and applying stamp powder which is light fast UV resistant pigment with appropriate chemical compounds of desired colour on base concrete after excess bleed water has evaporated using dry shake method @5kg per sqm. Including texturing, and covering with plastic sheet (min 200 micron thickness) and also applying two coats of UV-stable,30 % solidsclear sealer @ 150 to 250 gms per sqm using surface roller and protecting from fallingdust,dirt and curring by curring compound / by providing cement vata in cement Mortor 1:8 @ 0.6m x 0.6m center to center, admeasuring 80mm at bottom and 40mm at top withdepth of 75mm and maintaining the same throughout curing period by any other method approved by Engineer-incharge or Landscape architect etc. complete. (prior approval of superinteding Engineer will be necessary) SSR NO 54.01 / 513	3149	81	Rupees Three Thousand One Hundred FourtyNine Paise EightyOne Only	SMT	154866.71			As Above
7	11.48	ITEM NO. 7 Providing and fixing precast R.C.C cover without angle frame for path way of size 0.7 m x 0.65 m as per instructed by Engineering – In - Charge	2225	0	Rupees Two Thousand Two Hundred TwentyFive Only	SMT	25531.88			As Above

8	5.10	Item No 8 Providing and laying weep holes of 100 mm diameter PVC pipes as per drawing for abutment returns, return walls etc. Complete. SSR 17.37/132	559	65	Rupees Five Hundred FiftyNine Paise SixtyFive Only	RMT	2854.22			As Above
9	1.00	ITEM NO. 9 Material testing	1000	0	Rupees One Thousand Only	NOS	1000.00			As Above

Contractor /Agency

No.of Correction :

Mira-Bhaindar Municipal Corporation