MIRA-BHAINDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

Name of Work :- Providing & fixing furniture work at sub-regitrar office in ward no. 23 at bhaindar (w) in M.B.M.C. Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	97.20	Item No.1 Providing and fixing Full Height one side Wooden Partitions-laminate finish made with MR grade Plywood 12mm thick, nesesary support frames as directed. Finishing complete in all respects with melamine polish to all surafaces & beads, etc. as shown in the drawings Spec. As directed by Engineer-In-Charge.(Market Rate)	7275	0	Rupees Seven Thousand Two Hundred SeventyFive Only	SMT	707130.00			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	12.96	Item No.2 Providing and Fixing Rollar Blinds AMI Make or approved make & shade of 38mm round Aluminium channel with Blackout fabric & telting with chain (Ball) system with all necessary fixtures and fitting etc. complete. (Sample to be final by Engineer In-charge prior execution of work) (Bd-Q : Wood work) / 355	2259	60	Rupees Two Thousand Two Hundred FiftyNine Paise Sixty Only	SMT	29284.42			As Above
3	1.35	Item No.3 Providing and fixing Storage made of 18 mm thk plywood with all external surfaces finished with approved laminate of 1.0 mm thk & all internal surfaces finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.Spec. As directed by Engineer-In-Charge. SSR. RA	18597	0	Rupees Eighteen Thousand Five Hundred NinetySeven Only	SMT	25105.95			As Above

4	2.00	ITEM NO.4 Executive's Table @ 1800Lx900Dx750HT Providing & Fixing of Table @ 1800Lx900Dx750HT - TOP & GABLE END to be made of Membrane finish with soft water fall edges & curved panel & Decorated Anodized section MODESTY PANEL to be made of 18 mm thick Prelaminated particle board with PVC edge band as per drawing SSR NO. 51.21 / 355	18092	55	Rupees Eighteen Thousand NinetyTwo Paise FiftyFive Only	NOS	36185.10			As Above
5	2.00	ITEM NO.5 Providing & Arrangemnt of Mild Back, Normal Syncro Mechanism, Fixed Armerst, Gaslift for Seat height adjustment, Standard 5 prong P/Nylon Base with Leather Upholstery SSR NO. 51.42	10041	15	Rupees Ten Thousand FourtyOne Paise Fifteen Only	NOS	20082.30			As Above
6	3.00	Item No. 6 Providing & Arrangemnt of Mid Back, ECO CTS Mechanism, Fixed Armrest, Gas lift for Seat height adjustment, Standard 5-prong P/Nylon Base with Fabric Upholstery SSR No. 51.43	6848	0	Rupees Six Thousand Eight Hundred FourtySix Only	NOS	20538.00			As Above
7	25.00	Item No.7 Providing and fixing Handle 200mm Stainless Steel etc. complete.(Rounded Shape) SSR NO. 63 page no 531	90	30	Rupees Ninety Paise Thirty Only	NOS	2257.50			As Above
8	40.00	Item No.8 Providing and fixing Lock for sliding shutter etc. complete. SSR NO. 45 page no 530	170	10	Rupees One Hundred Seventy Paise Ten Only	NOS	6804.00			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation