MIRA-BHAINDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

Name of Work :- Providing & fixing partition , ceiling and other work at sub-regitrar office in ward no. 23 at bhaindar (w) in M.B.M.C. Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	60.75	ITEM NO.1 Providing and fixing False ceiling of 12 mm thick Laminated board with frame of M.S. angle 40 x 40 x 5 mm and Tee of size 40 x 40 x 6mm at 60 cm c/c including 12 mm dia. hangers, T.W. battens 50 x 25 mm and beading 25 x 15 mm thick scaffolding if necessary, all Iron work etc. complete SSR NO. 38.21	2556	75	Rupees Two Thousand Five Hundred Fifty Six and Seventy Five Paise Only	SMT	155322.56			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	12.00	Item No.2 Public Seating Chair. - 3 Seater Providing and Fixing 3 seater Public seating chair made of complete metal with Legs in Crome finish and seates in silver powder coating finish. SSR 51.44 / 359	18958	80	Rupees One Lac Eighty Nine Thousand Nine Hundred Fifty Eight & Eighty Paise Only	RMT	227505.60			As Above
3	33.21	Item No.3 Providing and fixing Full Height Wooden Partitions- laminate finish made with MR grade Plywood 12mm thick, nesesary support frames as directed. Finishing complete in all respects with melamine polish to all surafaces & beads, etc. as shown in the drawings Spec. As directed by Engineer-In-Charge.(Market Rate)	13216	0	Rupees One LacThree Thousand Two Hundred Sixteen Only	SMT	438903.36			As Above
4	8.10	Item No.4 Providing and fixing Storage made of 18 mm thk plywood with all external surfaces finished with approved laminate of 1.0 mm thk & all internal surfaces finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.Spec. As directed by Engineer-In-Charge. SSR. RA	18597	0	Rupees One Lac Eight Thousand Five Hundred Ninety Seven Only	SMT	25105.95			As Above

Contractor /Agency **No.of Correction :**

Executive Engineer
Mira-Bhaindar Municipal Corporation