MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

NAME OF WORK:- Providing and fixing tiles and paint work for Rest Room at morva smashanbhumi in ward no. 23 at Bhaindar (w.) in MBMC area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	10.07	ITEM NO. 1 Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete SSR 27.05 / 254	10027	16	Rupees Ten Thousand TwentySeven Paise Sixteen Only	CMT	101010.60			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	117.07	ITEM NO. 2 Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. SSR NO. 32.11 / 269	700	64	Rupees Seven Hundred Paise SixtyFour Only	SMT	82023.25			As Above
3	106.32	ITEM NO. 3 Providing and applying pearl/ luster finish paint of approved colour and shade to the existing plaster surface including scaffolding, preparing the surface, applying the acrylic wall putti etc. complete. SSR 35.23 / 288	226	80	Rupees Two Hundred TwentySix Paise Eighty Only	SMT	24113.38			As Above
4	117.07	ITEM NO. 4 Providing and applying two coats Apex Ultima Puranature Anti-Pollution Or equivalent approved brand, paint should decomposes organic substances and inorganic gases(NOx, VOC's, CO, SOx,formaldehydes, etc.) in presence of natural or artificial light. It contains Graphene and nanoparticles of titanium oxide. and Absorbs CO2 (4.8 Kilogram/15 l). plaster crack should be filled by Acrylic base Crack seal/Textured Crack filler, Paint has to applied on one coat of Apex Ultima Puranature Anti-Pollution Primer or Equivalent. Warranty Should be given by the Manufaturer The work should be done by the Manufacturer Recommended applicator and he should be able to furnish stage wise onsite technical reports from theconcerned company technologist SSR 50.79/ 346	390	60	Rupees Three Hundred Ninety Paise Sixty Only	SMT	45727.17			As Above

5	62.36	ITEM NO. 5 Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. SSR NO.33.06 / 213	1329	14	Rupees One Thousand Three Hundred TwentyNine Paise Fourteen Only	SMT	82885.17			As Above
6	64.02	ITEM NO. 6 Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1 Kg per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete. SSR NO. 31.04 / 150	1373	24	Rupees One Thousand Three Hundred SeventyThree Paise TwentyFour Only	SMT	87914.82			As Above

Contractor /Agency **No.of Correction :** **Executive Engineer**
Mira-Bhaindar Municipal Corporation