MIRA-BHAINDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

NAME OF WORK:- Proposed laying of stamp concrete at rai smashanbhoomi in ward no. 23 at Bhaindar (w.) in MBMC area.

Item No	Quantity as per Sanctioned Estimate	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	16.88	ITEM NO. 1 Removing cementtiles, or marble or polished shahabad flooror dado with out bed concrete including stacking the materials as directed with all leads, lifts etc. complete SSR 46.19	47	25	Rupees Forty Seven and Twenty Five Paise Only	CMT	797.58			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	16.88	ITEM NO.2 TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m. SSR Statement C-1	468	37	Ruppes Four Hundred Sixty Eight & Thirty Seven paise Only	CMT	7906.09			As Above
3	16.88	ITEM NO. 3 Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/ quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc). SSR NO. 24.10	8391	86	Rupeese Eight Thousand Three Hundred Ninety One & Eighty Six Paise Only	CMT	141654.60			As Above

4	296.80	ITEM NO. 4 Stamp Concrete of 100mm Thickness - Providing and Laying in-situ M30 Grade unreinforced plain cement stamp concrete of 100mm thickness pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate (natural sand / VSI grade finely washed crushed sand) Confirming to IS 383, as per mixed in a batching and mixing plant / non tilting mixer and weigh batcher as per approved mix design, admixtures, transporting to site in nagpur city with lead upto 20KM (on Inner Ring Road from Avasti nagar to wadi), spreading, laying with approved make pover, compacted and finished in a continous operation, finishing to lines and grades Also Providing, Placing and applying stamp powder which is light fast UV resistant pigment with appropriate chemical compounds of desired colour on base concrete after excess bleed water has evaporated using dry shake method @5kg per sqm. Including texturing, and covering with plastic sheet (min 200 micron thickness) and also applying two coats of UV-stable,30 % solidsclear sealer @ 150 to 250 gms per sqm using surface roller and protecting from fallingdust,dirt and curring by curring compound / by providing cement vata in cement Mortor 1:8 @ 0.6m x 0.6m center to center, admeasuring 80mm at bottom and 40mm at top withdepth of 75mm and maintaining the same throughout curing period by any other method approved by Engineer-incharge or Landscape architect etc. complete. (prior approval of superinteding Engineer will be necessary) SSR 54.01/513	1873	29	Rupees One Thousand Eight hundred Seventy Three & Twenty Nine Paise Only	SMT	555992.47			As Above
5	105.60	ITEM NO. 5 Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. SSR NO.33.06 / 213	1329	74	Rupees One Thousand Three Hundred Twenty Nine & Seventy Four Paise Only	SMT	140357.18			As Above

6		ITEM NO. 6TESTING								
	1.00	Compresive Strength (set of 3 cubes)	690	0	Rupees Six Hundred Ninety Only	No.s	690.00			As Above