MIRA-BHAYANDAR MUNICIPAL CORPORATION

SCHEDULE 'B'

NAME OF WORK: Proposed construction of pcc work at bhogilal chawl baman dev in word no 13 in mira road E ,IN MBMC AREA

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	57.51	ITEM NO 01 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR 21.02 / 189	217	35	Rupees Two Hundred Seventeen Paise Eighty Five Only	CMT	12499.80			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	57.51	ITEM NO 02 TRANSPORTING OF EXCAVATED MATERIALS lead 20.00 k.m. SSR in Statement C 1 (Page 717)	468	37	Rupees Four Hundred Sixty Eight Paise Thirty Seven Only	CMT	26935.96			As Above
3	28.76	ITEM NO 03 Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. SSR 21.38 / 194	3240	42	Rupees Three Thousand Two Hundred Forty Paise Fifty Forty two Only	CMT	93178.28			As Above

4	28.76	ITEM NO 4 Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/ quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) (PCC) SSR 24.10 / 216	8391	86	Rupees Eight Thousand Three Hundred Ninety One Paise Eighty Six Only	CMT	241307.93			As Above
5	1.00	ITEM NO.16 Testing Charges	690	0	Rupees Six Hundred Ninety Only	No.s	690.00			As Above
6	28.76	ITEM NO.17 Royalt Charges	216	18	Rupees Two Hundred Sixteen Paise Eighteen Only	NOS	6216.26			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation