MIRA-BHAYANDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

Name of Work :- Proposed providing and fixing stainless steel railing at Jesal park Footpath in Ward No.02 Bhaindar (E) in MBMC Area

Item No	Quantity as per Sanctioned Estimate	Item of Work	Estimated Rate			Unit	Total Amount according to estimated quantities	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	1162.66	Item No.1 Providing and fixing stainless steel (Grade 304) railing made of hollow tubes, channels, plates etc. including welding grinding, buffing polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories and stainless steel dash fasteners, stainless steel bolts, etc. of the required size on the top of the floor of the side of waiste slab with suitable arrangement as per approval of engineer in charge (for payment purpose, only the weight of the stainless steel members shall be considered excluding fixing accessories such as nut bolts, fasteners etc.). 50mm dia. pipe, 1.5mm thickness and weight 1.92 kg / r. metre S S R 51.73/270	728	70	Rupees Seven Hundred TwentyEight Paise Seventy Only	kg	847230.34			As per Instruction given by Executive Engineer/ Site Engineer during execution of work

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhayandar Municipal Corporation