MIRA-BHAINDAR MUNICIPAL CORPORATION
SCHEDULE 'B'

Name of Work :- Proposed Construction of Stainless steel Bus Stop at Prafull patil chowk, Indralok naka in ward no. 10 Bhainder (E.) in MBMC Area.

Item No	Quantity as per Sanctioned	Item of Work	Estimated Rate			Unit	Total Amount according to estimated	Specification		Additional Specification
			In Figures		In Words			Clause No	Page No	
			Rs.	Ps.	Rs.					
1	2	3	4	5	6	7	8	9	10	11
1	0.24	ITEM NO. 1 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area & stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR 21.02 / 197	191	10	Rupees One Hundred NinetyOne Paise Ten Only	Cu.Mt.	46.44			As per Instruction given byExecutive Engineer/ Site Engineer during execution of work
2	0.19	ITEM NO.2 TRANSPORTING OF EXCAVATED MATERIALS lead 3.00 k.m. SSR Statement C-1	387	66	Rupees Three Hundred EightySeven Paise SixtySix Only	Cu.Mt.	75.36			As Above

3	8.78	ITEM NO. 3 Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) SSR 24.08 / 227	7229	73	Rupees Seven Thousand Two Hundred TwentyNine Paise SeventyThree Only	Cu.Mt.	63440.88			As Above
4	459.03	ITEM NO. 4 Providing and fixing stainless steel (Grade 304) railing made of hollow tubes, channels, plates etc. including welding grinding, buffing polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories and stainless steel dash fasteners, stainless steel bolts, etc. of the required size on the top of the floor of the side of waiste slab with suitable arrangement as per approval of engineer in charge (for payment purpose, only the weight of the stainless steel members shall be considered excluding fixing accessories such as nut bolts, fasteners etc.). 50mm dia. pipe, 1.5mm thickness and weight 1.92 kg / r. metre SSR 51.73	728	70	Rupees Seven Hundred TwentyEight Paise Seventy Only	KG	334492.68			As Above

5	19.68	ITEM NO. 5 Providing,aupplying,fabricating and fixing panel of aluminium composite panel cladding in approved shape made out of 4 mm thick ACP sheet material consisting of 3mm thick FR grade mineral core following NBC part IV Fire and life safety (having 2 hours fire resistance in accordance to ASTM E119-12 and BS476 part 6 and 7 class O) sandwitched between two aluminium sheets (each 0.5 mm thick of AA 5005/AA3105 grade) The aluminium composite panel cladding sheet shall be coil coated with kynar 500 based PVDF/ Lumiflon based fluropolymer resin (having 70:30 ratio of PVDF and acrylic) coating of approved colour and sg=hade on top face and polymer (service) coating of bottom face as specified using stainless steel Screws,nuts,bolts,washers,cleats,weather silicon sealent,backer rods etc .overall weight of the ACP shall not be less than 7.5 kg/sqm) SSR 51.10	4063	50	Rupees Four Thousand SixtyThree Paise Fifty Only	SMT	79969.68			As Above
6	2.00	ITEM NO. 6 Testing	1000	0	Rupees One Thousand Only	No.	2000.00			As Above

Contractor /Agency

No.of Correction :

Executive Engineer
Mira-Bhaindar Municipal Corporation