



## मिरा भाईदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८  
**बांधकाम / विद्युत विभाग**

जा.क्र. मनपा/साबां/७६ /२०२५-२६  
दि.०७/११/२०२५

प्रति,  
सिस्टीम मॅनेजर  
माहिती तंत्रज्ञान विभाग  
मिरा भाईदर महानगरपालिका

**विषय :-** जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

मिरा भाईदर महानगरपालिका क्षेत्रातील आरक्षण क्र. १२२ येथे स्व. बाळासाहेब ठाकरे कलादालन बांधणे करीता बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

(नितिने मुकणे)  
कार्यकारी अभियंता (साबां/वि)  
मिरा भाईदर महानगरपालिका



## मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८  
बांधकाम / विद्युत विभाग


जा.क्र. मनपा/साबा/७६ /२०२५-२६

दि.०७/११/२०२५

### // जाहिर नोटीस //

मिरा भाईंदर महानगरपालिका क्षेत्रातील आरक्षण क्र. १२२ येथे स्व. बाळासाहेब ठाकरे कलादालन बांधणे कामी चालु जिल्हा दरसूचीमध्ये दर उपलब्ध नसल्यामुळे खुल्या बाजारातून दरपत्रक मागविण्यात येत आहे.

सदर कामाकरिता दि. १४/११/२०२५ रोजी संध्या ४.०० वाजेपर्यंत मिरा भाईंदर महानगरपालिका, मुख्य कार्यालय, बांधकाम विभाग, ४ था मजला येथे स्वारस्य असलेल्या कंत्राटदाराने सोबत जोडलेल्या दरपत्रकातील बाबींकरिता दर भरून देण्यात यावेत.

  
(नितिन मुकणे)  
कार्यकारी अभियंता (साबां/वि)  
मिरा भाईंदर महानगरपालिका



**MIRA BHAINDAR MUNICIPAL CORPORATION**  
Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,  
Bhaindar (W) 401101, Tal. Dist - Thane, 28192828  
**PWD/ELECTRIC DEPARTMENT**

**// RATE FORM //**

**Name of Work :- Proposed Construction of Hindu Hriday Smrat Balasaheb Thackeray Art Gallery at Rev.122 Bhayandar (E) in MBMC Area.**

**Name and address of Contractor :-**

Sr. No.	DESCRIPTION	Rate Por Unit in INR	Quantity	Amount (In INR)
1.	Providing and applying premium grade Synthetic Varnish paint of approved quality, colour and shade to new surface in including perfect leveling , clening, preparing the surface. etc. complete.	Sqm	1.00	
2.	Providing and fixing : High impact surface mount Corner Guard having Vinyl: Snap on cover of .080" (2mm) thickness shall be extruded from chemical and stain resistant polyvinyl chloride with the addition of impact modifiers No plasticizers shall be added (plasticizers may aid in bacterial growth). Surface shall have a pebblette texture for scratch resistant. Continuous aluminum retainer of .070" (1.8mm) thickness shall be fabricated from 6063-T5 aluminum, with a mill finish. Dimensions to be of 3" (76mm) x 3" (76mm), 90 degree. The rigid vinyl profile shall resist an impact of 30.2 ft-lbs/inch as per ASTM D-256-90b and shall not support fungal or bacterial growth inaccordance with ASTM G-21 and G-22. The system shall also conform to class A fire rating and ASTM D-543 for chemical and stain resistance. It includes Top caps and bottom caps which shall be made of injection molded thermoplastics. as Directed by Engineer Incharge.	RMT	1.00	

3.	Providing and applying premium grade royale/velvet acrylic emulsion paint of approved quality, colour and shade to new surface in two coats including primer ,putty,primer with perfect leveling , clening, preparing the surface. etc. complete.	Sq,m	1.00	
4.	Providing & fixing STEP LIGHT UP - DOWN THROW WITH BOTH SIDE NO. SIZE 0.8 MTR 12V/12.5 AMP MEANWELL SMPS With LASER ENGRAVED SEAT NUMBER PLATS etc Complete	Nos	1.00	
5.	Providing and constructing RCC Inspection Chamber 90cm x 60cm including RCC cement concrete foundation RCC Pardi, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover Heavy duty 4ton with frame etc complete	Nos	1.00	
6.	Providing and constructing RCC Inspection Chamber 90cm x 90cm including RCC cement concrete foundation RCC Pardi, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover Heavy duty 4ton with frame etc complete	Nos	1.00	
7.	Providing and constructing RCC Inspection Chamber 60cm x 60cm including RCC cement concrete foundation RCC Pardi, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover Heavy duty 4ton with frame etc complete	Nos	1.00	
8.	Providing Alumminium Scaffolding of Height 10.5 Mt for maintainance work Including HORIZONTAL BRACE, PUSH ON FRAME, STAIRWAY ETC, completed	Nos	1.00	
9.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 1 C X 70 Sq. mm.YWY XLPE	Rmt	1.00	
10.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers /	Rmt	1.00	

	saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 1 C X 95 Sq. mm.YWY XLPE			
11.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Shielded Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 4 C X 1.5 Sq. mm.YWY XLPE	Rmt	1.00	
12.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 4 C X 2.5 Sq. mm.YWY XLPE	Rmt	1.00	
13.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 3 C X 2.5 Sq. mm.YWY XLPE	Rmt	1.00	
14.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Aluminium Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 3.5 C X 70 Sq. mm. A X F Y XLPE	Rmt	1.00	

15.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Aluminium Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 3.5 C X 35 Sq. mm. A X F Y XLPE	Rmt	1.00	
16.	SITC of 1100 V grade XLPE insulated sheathed & steel armoured Aluminium Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 3.5 C X 25 Sq. mm. A X F Y XLPE	Rmt	1.00	
17.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 4 C X 6 Sq.mm. YWY XLPE	Rmt	1.00	
18.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 4 C X 4 Sq. mm. YWY XLPE	Rmt	1.00	

19.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical, heavy duty brass glands, crimping sockets including 3 C X 4 Sq.mm. YWY XLPE	Rmt	1.00	
20.	SITC of 1100 V grade XLPE insulated sheathed & steel Flexible Copper Conductor cables. Unloading by crane, shifting to place of work and laid on walls / ceiling / ready made trench / Cable tray / Through underground RCC pipes / including spacers / saddles / clamps / G.I. Hardware as required, (M.S. cable trays supports / cable trays, RCC pipes covered by seperate items ) with Termination of cable using screwed flange type elliptical / conical,, crimping sockets including 4 C X 2.5 Sq. mm.YWY XLPE	Rmt	1.00	
21.	Supply And erecting 12 W COB LED & EXTRUDED ALUMINIUM HOUSING For Decorevite purpose	Nos	1.00	
22.	Supply & erecting of 2.5 m liberty type decorative doble Arm Aluminum Diecast Lamp post with Foundation Nut Bolt and anchor plate	Nos		

कंपनीचा सही व शिक्का