



# मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

बांधकाम / विद्युत विभाग

७६३७

जा.क्र.मनपा/साबां/विद्युत/ क. ३-२ /2025-26

दि. २१ / ०१ / 2026

प्रति,

जनसंपर्क अधिकारी

जनसंपर्क विभाग

मिरा भाईंदर महानगरपालिका

**विषय :-** फेर जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

उपरोक्त विषयांकित मिरा भाईंदर महानगरपालिका क्षेत्रात विविध देखभाल दुरुस्ती विषयक कामे देण्यात आलेले आहेत.

- 1) मिरा भाईंदर महानगरपालिकेच्या स्मशानभूमीतील शवदाहीन्या, चिमनी एअर एक्झॉस्ट सीस्टीम यांची व्दिवार्षिक मुदतीने देखभाल व दुरुस्ती करणे. (ऑपरेटर / कर्मचारी पुरवठा व संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)
- 2) मिरा भाईंदर महानगरपालिकेची मुख्य कार्यालय, प्रभाग कार्यालय इ. रेन्टल हाऊसिंग, सक्रमण शिबिरे, सबवे, उड्डाणपूल, पाण्याच्या टाक्या, स्कायवॉक, सार्वजनिक सभागृह, वाचनालय, आयुक्त / महापौर निवास, अभ्यासिका विरंगुळा केंद्र समाज मंदिरे, बालवाड्या, शाळा आंगणवाडी, चौपाट्या, आरोग्य केंद्र, हॉस्पिटल, स्मशानभूमी, दफनभूमी इ. मैदाने उद्याने तलाव व फुट ओवर ब्रिज, सबवे, वाहतूक बेट मधिल सर्व विद्युत दुरुस्ती, मीटर पंप दुरुस्ती इ. देखभाल व दुरुस्तीचे कामे वार्षिक मुदतीने करणे.
- 3) मिरा भाईंदर महानगरपालिका क्षेत्रातील विविध सार्व. इमारतीवरील सोलार पॉवर प्लांट यंत्रणा व्दिवार्षिक मुदतीने देखभाल दुरुस्ती करणे. (संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)

सदर कामी सोबत जोडण्यात आलेली कोटेशन नोटीस महानगरपालिकेच्या अधिकृत संकेत स्थळावर तसेच स्थानिक वृत्तपत्रांमध्ये प्रसिध्द / upload करण्यात यावी.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका



# मिरा भाईदर महानगरपालिका



स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

बांधकाम / विद्युत विभाग

०६३०

जा.क्र. मनपा/साबां/विद्युत/क.अ-२ /2025-26

दि. २१/०१/2025

प्रति,

सिस्टीम मॅनेजर

माहिती तंत्रज्ञान विभाग तथा जनसंपर्क अधिकारी

मिरा भाईदर महानगरपालिका

**विषय :-** फेर जाहीर सुचना वृत्तपत्रात व महानगरपालिकेच्या संकेतस्थळावर प्रसिध्द करणेबाबत.

उपरोक्त विषयांकित मिरा भाईदर महानगरपालिका क्षेत्रात विविध देखभाल दुरुस्ती विषयक कामे देण्यात आलेले आहेत.

- 1) मिरा भाईदर महानगरपालिकेच्या स्मशानभूमीतील शवदाहीन्या, चिमनी एअर एक्झॉस्ट सीस्टीम यांची व्दिवार्षिक मुदतीने देखभाल व दुरुस्ती करणे. (ऑपरेटर / कर्मचारी पुरवठा व संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)
- 2) मिरा भाईदर महानगरपालिकेची मुख्य कार्यालय, प्रभाग कार्यालय इ. रेन्टल हाऊसिंग, सक्रमण शिबिरे, सबवे, उड्डाणपूल, पाण्याच्या टाक्या, स्कायवॉक, सार्वजनिक सभागृह, वाचनालय, आयुक्त / महापौर निवास, अभ्यासिका विरंगुळा केंद्र समाज मंदिरे, बालवाड्या, शाळा आंगणवाडी, चौपाट्या, आरोग्य केंद्र, हॉस्पिटल, स्मशानभूमी, दफनभूमी इ. मैदाने उद्याने तलाव व फुट ओवर ब्रिज, सबवे, वाहतूक बेट मधिल सर्व विद्युत दुरुस्ती, मीटर पंप दुरुस्ती इ. देखभाल व दुरुस्तीचे कामे वार्षिक मुदतीने करणे.
- 3) मिरा भाईदर महानगरपालिका क्षेत्रातील विविध सार्व. इमारतीवरील सोलार पॉवर प्लांट यंत्रणा व्दिवार्षिक मुदतीने देखभाल दुरुस्ती करणे. (संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)  
सदर कामी सोबत जोडण्यात आलेली कोटेशन नोटीस महानगरपालिकेच्या अधिकृत संकेत स्थळावर तसेच स्थानिक वृत्तपत्रांमध्ये प्रसिध्द / upload करण्यात यावी.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/विद्युत)

मिरा भाईदर महानगरपालिका



## मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

### बांधकाम / विद्युत विभाग

०६३०

जा.क्र. मनपा/साबां/विद्युत/क.अ-२/2025-26

दि. २१/०१/2026

### // फेर जाहिर नोटीस //

मिरा भाईंदर महानगरपालिका क्षेत्रात विविध देखभाल दुरुस्ती विषयक कामे देण्यात आलेले आहेत.

- 1) मिरा भाईंदर महानगरपालिकेच्या स्मशानभूमीतील शवदाहीन्या, चिमनी एअर एक्झॉस्ट सीस्टीम यांची व्दिवार्षिक मुदतीने देखभाल व दुरुस्ती करणे. (ऑपरेटर / कर्मचारी पुरवठा व संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)
- 2) मिरा भाईंदर महानगरपालिकेची मुख्य कार्यालय, प्रभाग कार्यालय इ. रेन्टल हाऊसिंग, सक्रमण शिबिरे, सबवे, उड्डाणपूल, पाण्याच्या टाक्या, स्कायवॉक, सार्वजनिक सभागृह, वाचनालय, आयुक्त / महापौर निवास, अभ्यासिका विरंगुळा केंद्र समाज मंदिरे, बालवाड्या, शाळा आंगणवाडी, चौपाट्या, आरोग्य केंद्र, हॉस्पिटल, स्मशानभूमी, दफनभूमी इ. मैदाने उद्याने तलाव व फुट ओवर ब्रिज, सबवे, वाहतूक बेट मधिल सर्व विद्युत दुरुस्ती, मीटर पंप दुरुस्ती इ. देखभाल व दुरुस्तीचे कामे वार्षिक मुदतीने करणे.
- 3) मिरा भाईंदर महानगरपालिका क्षेत्रातील विविध सार्व. इमारतीवरील सोलार पॉवर प्लांट यंत्रणा व्दिवार्षिक मुदतीने देखभाल दुरुस्ती करणे. (संपुर्ण कॉम्प्रेन्सिव्ह पध्दतीने)

सदर कामे करण्याकामी कामी चालु जिल्हा दरसुचीमध्ये दर उपलब्ध नसल्यामुळे खुल्या बाजारातुन दरपत्रक मागविण्यात येत आहे.

सदर कामाकरिता दि. २१/०१/2026 रोजी संध्या 4.00 वाजेपर्यंत मिरा भाईंदर महानगरपालिका, मुख्य कार्यालय, बांधकाम विभाग, 4 था मजला येथे स्वारस्य असलेल्या कंत्राटदाराने सोबत जोडलेल्या दरपत्रकातील बाबींकरिता दर भरून देण्यात यावेत.

सदर कामी विस्तृत माहिती [www.mbmcc.gov.in](http://www.mbmcc.gov.in) या संकेतस्थळावर उपलब्ध आहे.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका



**MIRA BHAINDAR MUNICIPAL CORPORATION**  
**PWD / Electric Department**  
**Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,**  
**Bhaindar (W) 401101,**  
**Tal. Dist – Thane, Ph. 28192828**

**// RATE FORM //**

**Name of Work :-** Rate for Maintenance of Lpg cremature, Air exhaust system (chimany) at various cementries in MBMC area.

**Name and address of Contractor :-**

**B-2 FORM**

Sr. No.	Description	Qty	UNIT	RATE
1)	<b>Item no.1</b> Skilled Labour for ooperate, maintenance of blower, exhaust, motor & chimney etc on 24*7 basis job includes blower proper running, cleaning & servicing of blower, motor, exhaust, electrical panel etc.Cleaning Of Smashanbhumi Area for Electrical, LPG And Wooden Crematorium	1.00	Month	
2)	<b>Item no.2</b> Comrehensive Maintenance and Operation Of Electric Crematorium and LPG crematorium at smashanbhumi & Air Exhaust System in MBMC area. Scope Of Work Include With Multi electric furnace and Multi scruber unit & Required chemney. 1) including all Electric periodical maintenance, Repairing of Electromechanical Equipements of System, switch gears, accessories, internal bed bricks and heating Elements (Coil) , Temp. Controller, Thermocouple Switches, Spray Nozzel, Chain, Trolly, Bearing, Insulation lining for door and required ,material fixture, tools etc. 2) accessories and includes all repairs and maintenance of DG Set with B check on every six months. Filling of required fuel (Diesel) in DG for operation with maintain the level of fuel to operate DG for minimum Eight hours, Maintenance of all consumable Parts of oil Filters, fuel filters, Belt and Servicing /includes daily checkup of all system and maintaining daily. 3) Submitting monthly report of crematorium to concern officer. 4) Include All Work of Existing Old Rusted and Damaged Exhaust Hood Removing And Replacing New Required Exhaust Hood Fitting with All New Ducting Pipes and Exhaust Motor work. 5) Compulsary Providing High Resistance Temperature paint on All System in Every 6 Month Interval. 6) Including Every 3 Month Interval Cleaning and Overhauling Of	1.00	Month	

	<p>Ducting Pipes, Scrubber Systems, Chimney System And Electrical panels For Operating Blower Pump Motor Process Applied for Electrical Crematorium,LPG Crematorium And Wooden Creamtorium System.</p> <p>7) Payment of labours will be made seprately Management and Maintenance (Parichalan) of at cementary in MBMC area.</p> <p>8) Complaint Should Be Resolve in 7 Days.</p>			
--	---	--	--	--

PC-03/2025-26/AB/Rate Form-06



**'MIRA BHAINDAR MUNICIPAL CORPORATION**  
**PWD / Electric Department**  
**Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,**  
**Bhaindar (W) 401101,**  
**Tal. Dist – Thane, Ph. 28192828**

**// RATE FORM //**

**Name of Work :-** RATE FOR ANNUAL MAINTENANCE WORKS OF ELECTRICAL, PLUMBING AT HEAD OFFICE, WARD OFFICES, RENTAL HOUSING BUILDING, TRANSIT CAMP, SUBWAY, FOB, SKYWALK, SAMAJ MANDIR, LIBRARY, SCHOOLS, HOSPITALS, CREMATION, COMMISSIONER BANGLOW, MAHILA BHAVAN, CHOWPATY, SELFI POINT ETC. IN MBMC AREA.

**Name and address of Contractor :-**

**B-2 FORM**

<b>Sr. No.</b>	<b>Description</b>	<b>Qty</b>	<b>UNIT</b>	<b>RATE</b>
1)	Item No.1 (MR) Supplying and erecting 25 mm Tee, bend, union & elbow etc for supporting of plumbing work.	1.00	Nos	
2)	Item No.2 (MR) Supplying and erecting of water out put stand with at position with necessary materials.	1.00	Nos	
3)	Item No.3 (MR) Repairing of electric motor pump of all type and makes above 1 HP to 2 HPwith replacing ball bearing, bush bearing, screws etc	1.00	Nos	
4)	Item No.4 (MR) Repairing of electric motor pump of all type and makes above 3 HP to 5 HPwith replacing ball bearing, bush bearing, screws etc.	1.00	Nos	
5)	Item No.5 (MR) Repairing of submersible motor pump of all type and makes above 1 HP to 5 HPwith replacing ball bearing, bush bearing, screws etc.	1.00	Nos	
6)	Item No.6 (MR) Supplying and fixing PVC Neppal.	1.00	Nos	
7)	Item No.7 (MR) Supplying and fixing Union dia. 50 mm with all necessary materials.	1.00	Nos	
8)	Item No.8 (MR) Supplying and fixing Coplmg dia. 50 mm with all necessary materials	1.00	Nos	
9)	Item No.9 (MR) Supplying and fixing Bend dia. 50 mm with all necessary materials	1.00	Nos	
10)	Item No.10 (MR) Supplying and fixing Elbow dia. 50 mm with all necessary materials	1.00	Nos	
11)	Item No.11 (MR) Supplying and erecting C.I. Bend 75/80 mm dia mtr. with necessary material as per site requirement.	1.00	Nos	
12)	Item No.12 (MR) Supplying and fixing 65mm PVC flexible Pipe.	1.00	Nos	

13)	Item No.13 (MR) Supplying and fixing 80mm PVC flexible Pipe.	1.00	Nos	
14)	Item No.14 (MR) Supplying and fixing 110mm PVC flexible Pipe.	1.00	Nos	
15)	Item No.15 (MR) Supplying and fixing 40mm PVC Pipe.	1.00	Nos	
16)	Item No.16 (MR) Supplying and fixing 25mm PVC Pipe.	1.00	Nos	
17)	Item No.17 (MR) Removing the sunction pipe line and cleaning the footvalve and minor repairs of electrical part of the site.	1.00	Nos	
18)	Item No.18 (MR) Providing Cement concrete work for cable trunch size 100 cm x 40 cm x 10cm with necessary curing and finishing in an appvd manner on the top.	1.00	Nos	
19)	Item No.19 (MR) Supplying and erecting G.I. foundation bolt size 3000 mm x 25 mm with base plate.	1.00	Nos	
20)	Item No.20 (MR) Erection the 9 meter long pole with 4 way decorative bracket and 4 Light fitting set in instruction of site Engineer.	1.00	Nos	
21)	Item No.21 (MR) Supplying of Decorative Street light bracket suitable for 4 x 250 W HPSV/ LED Street light set with all necessary materials as per site requirement.	1.00	Nos	
22)	Item No.22 (MR) Supplying and fixing meter box for single phase with removing the damaged box with all necessary materials	1.00	Nos	
23)	Item No.23 (MR) Supplying and fixing meter box for three phase with removing the damaged box with all necessary materials	1.00	Nos	
24)	Item No.24 (MR) Supplying and fixing of the street light PVC cover fixing on the top at the site with all attachment.	1.00	Nos	
25)	Item No.25 (MR) Shifting of fans, tube light & boards with all needed materials including all charges.	1.00	Nos	
26)	Item No.26 (MR) Cleaning of ceilling fan	1.00	Nos	
27)	Item No.27 (MR) To remove the gate lamp after disconnection of electricity & cleaning by surf water then refixing the same as per site requirement.	1.00	Nos	
28)	Item No.28 (MR) Supplying and erecting pipe post made from ISI mark G.I. pipe 50 mm. dia 3 meter overal length, with two bends, fixed to pipe at the top / round bended, complete erected with M.S. flat welded wall with necessary clamps, nuts and bolts etc. duly painted with two coats of aluminium paint complete.	1.00	Nos	
29)	Item No.29 (MR) Supplying and erecting pipe post for street light made from ISI mark G.I. pipe 75 mm. dia 3meter over all length, complete erected with M.S. flat welded wall with necessary clamps, nuts and bolts etc. duly painted with two coats of aluminium paint complete.	1.00	Nos	

30)	Item No.30 (MR) Attending the complaint & minor fault repairs.	1.00	Nos	
31)	Item No.31 (MR) Supplying and erecting ISI mark midget type 3.0 Ltr Instant type water heater of ABS plastic body 3 KW coming IS3412 heating element 230/250 V 50 cycle A.C. supply with inlet & outlet	1.00	Nos	
32)	Item No.32 (MR) Supplying and erecting storage type vertical water heater flow rate 1.8 to 10 ltr / min, 5500 W 230 V, 50 Hz AC and size 360mm X 120mm X 260mm with high impact resistance body on wall.	1.00	Nos	
33)	Item No.33 (MR) Supplying and erecting Street light bracket for erection of Tripal fitting made from 40 mm. dia 'B' class G.I. pipe 0.6 m in length along with pole cap of 300 mm length 100 mm dia duly welded.	1.00	Nos	
34)	Item No.34 (MR) Supplying & erecting Street light bracket suitable for Alu. street light with all necessary materials as per site requirement.	1.00	Nos	
35)	Item No.35 (MR) Supplying & erecting bracket for single fitting made from 25 mm. dia B class G.I pipe duly welded as with MS structures.	1.00	Nos	
36)	Item No.36 (MR) Meter Liationing charges	1.00	Nos	
37)	Item No.37 (MR) Supplying and erecting Timmer switch.	1.00	Nos	
38)	Item No.38 (MR) Supplying and erecting 32A Single pole 230 VAC contactor	1.00	Nos	
39)	Item No.39 (MR) Supplying and erecting 63 A 4 pole 415 VAC contactor	1.00	Nos	
40)	Item No.40 (MR)) Supplying and erecting 100A 4 pole 415VAC contactor	1.00	Nos	
41)	Item No.41 (MR) Supplying and erecting PVC Water tank 1000 ltr on suitable foundation.	1.00	Nos	
42)	Item No.42 (MR) Make the provision in the window frame and remove the glass and fix the 18 mm waterproff ply suitable for exasust fan	1.00	Nos	
43)	Item No.43 (MR) Supplying and erecting of plumbing work inlet connection with outlet connection for vertical water heater with stop cork, pipe, nipple, Tee, bend, connector clamp etc.	1.00	Nos	
44)	Item No.44 (MR) Removing the 20 HP submersible motor pump after vacant water tank with help of other motor pump and refixing the same motor with help of chain and man power.	1.00	Nos	
45)	Item No.45 (MR) Repairing of autometric control panel for 3 Ph, 415 volt, A. c. Submersible/Centrifugal pump set upto 20 HP with relay range 26-42 AMP, S.P.P., Combined ammeter/ voltmeter, phase indicating lamp including labour charges.	1.00	Nos	
46)	Item No.46 (MR) Supply of 150 bar Portable pressure washer, 230V, single phase 50 cycle A.C. supply of 1 HP of specified discharge 9.6 LPM suction capacity.	1.00	Nos	
47)	Item No.47 (MR) Supply of High Pressure water Spray Gun.	1.00	Nos	

48)	Item No.48 (MR) Supplying & erecting approved make white stove enamelled/ powder coated CRCA sheet not less than 0.7 mm thick chalk board type fluo fitting of 2 x 28W T5 with Electronic ballast, having pf > 0.9 fixed in false ceiling or on wall as per specification No. FG-IDF/MOP	1.00	Nos	
49)	Item No.49 (MR) Supply and Installation for IP 2MP Bullet Outdoor Camera as per the Technical Specifications	1.00	Nos	
50)	Item No.50 (MR) Supply and Installation for 16 channel NVR	1.00	Nos	
51)	Item No.51 (MR) Supply and Installation 4TB Interna; SATA Hard Drive	1.00	Nos	
52)	Item No.52 (MR) Supplying and erecting 8 Port OOE switch	1.00	Nos	
53)	Item No.53 (MR) Supplying and erecting 32" inch LED TV	1.00	Nos	
54)	Item No.54 (MR) Supplying and erecting outdoor weatherproof box for switch	1.00	Nos	
55)	Item No.55 (MR) Yearly Supply of Security cum Operator cum Electrician at Shahid Bhagat Singh subway near Jessal park in MBMC area. (Total Operator per day are 3, and total days 365) 3 X 365 days = 1095 units	1.00	Nos	



**MIRA BHAINDAR MUNICIPAL CORPORATION**  
**PWD / Electric Department**  
**Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,**  
**Bhaindar (W) 401101,**  
**Tal. Dist – Thane, Ph. 28192828**

**// RATE FORM //**

**Name of Work :-** RATE FOR TWO YEARLY COMPRENSIVE REPAIRING & MAINTENANCE WORK OF ALL SOLAR POWER PLANT AT DIFFERENT LOCATION AT WARD NO.1 TO 6 AT VARIOUS LOCATION IN MBMC AREA.

**Name and address of Contractor :-**

**B-2 FORM**

<b>Sr. No.</b>	<b>Description</b>	<b>Qty</b>	<b>UNIT</b>	<b>RATE</b>
1)	ItemNo.1 Providing Repairing & Maintenance work of Solar power plant at various Places in MBMC Area. (Comprehensive work) including Servicing and cleaning 2 times in a month as per requirement and instructed by engineer incharge to maintain Solar power plant in working condition with All NecessaryConnector Wires, Inverter, Battery, UPS system, Electrical & Civil Work with require items as per instructed by Engineer incharge. (Fully Comprehensive work) 1) Monthly servicing 2) on call repair 3) replacement of all spares within 24 hours 4) The job include sheet metal work and plastic material with Electrical Parts 5) Battery Servicing 6) Battery Terminal Cleaning 7) UPS System Servicing 8) Solar panel Connecting Cables	1.00	month	