



मिरा-भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

पाणी पुरवठा व मलनिःसारण विभाग

संकेतस्थळ - www.mbmc.gov.in

ई-मेल - watersupply@mbmc.gov.in

संपर्क - 281922828-251



जा.क्र.मनपा/पापु व मलनि/क.अ.६/१६७५ /२०२५-२६

दि.१०/०९/२०२५

प्रति,
सिस्टम मॅनेजर
संगणक विभाग
मिरा-भाईंदर महानगरपालिका

विषय :- मिरा भाईंदर महानगरपालिकेच्या साकेत पंपिंग स्टेशन मधील VFD पॅनल क्र.03 व 600 HP VT पंप सेट क्र.05 ची दुरुस्ती करणे कामाचे अंदाजपत्रक तयार करणेकरीता ऑन-लाईन दर मागविणेबाबत.

मिरा भाईंदर महानगरपालिकेच्या साकेत पंपिंग स्टेशन मधील VFD पॅनल क्र.03 व 600 HP VT पंप सेट क्र.05 ची दुरुस्ती करणे कामाची निविदा मागविणेकरीता अंदाजपत्रक तयार करावयाचे आहे. परंतु सदर कामाअंतर्गत नमुद बाबींकरिताचे दर दरसुचीमध्ये उपलब्ध नसल्याने ऑन-लाईन दर www.mbmc.gov.in या संकेत स्थळावर मागविणे करीता सोबत जोडलेल्या बाबींचा तक्ता आनलाईन प्रसिध्द करण्यात यावा.

शहर अभियंता
मिरा-भाईंदर महानगरपालिका



मिरा-भाईदर महानगरपालिका

पाणी पुरवठा व मलनिसारण विभाग

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईदर(प)

ता. जि.ठाणे - ४०१ १०१



मिरा भाईदर महानगरपालिकेच्या साकेत पंपिंग स्टेशन मधील VFD पॅनल क्र.03 व 600 HP VT पंप सेट क्र.05 ची दुरुस्ती करणे या कामाचे अंदाजपत्रक तयार करणेकमी मिरा-भाईदर महानगर पालिका खालील तक्त्यातील बाबींकरिता ऑनलाईन दर मागवीत आहे.

उपरोक्त कामांतर्गत बाबींचे दर दि. 9.09.2025 ते दि. 16.09.2025 रोजी दुपारी 12.00 वाजेपर्यंत watersupply@mbmc.gov.in या ई-मेलवर पाठविण्यात यावे.


DESCRIPTION OF WORK	Aprox Qty	Unit	Rate (Excluding GST)
SUB WORK A - REPAIRS OF SIEMENS VFD PANEL NO 3 AT SAKET WATER PUMPING STATION			
ITEM No 1 :- Supply, Erection, Testing & Commissioning of Cim Control Interface Module- (G130, S120) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	1		
ITEM No 2 :- Supply, Erection, Testing & Commissioning of Fan (Complete Assembly Kit) For Ac Drive/Power/Motor Module Frame Sizes G, H And J) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	2		
ITEM No 3 :- Supply, Erection, Testing & Commissioning of Fan Transformer For 3ac 380-480 V Framesize H) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	1		
ITEM No. 4:- Supply, Erection, Testing & Commissioning of Thyr_ Tz800n 1800v 800a) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	6		
ITEM No. 5:- Supply, Erection, Testing & Commissioning of Igd3/R2 Mod. 480v/840a) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	3		
ITEM No. 6:- Supply, Erection, Testing & Commissioning of Capacitor 5200u 20% 400v 85c) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	24		
ITEM No.7:- Supply, Erection, Testing & Commissioning of Tdb Bgr R6 480v Ac (J2s309856)) etc complete as directed by Engineer-In-Charge & as per detailed specifications.	1		

SUB WORK B - REPAIRS TO 600 HP VT PUMP SET NO 5 AT SAKET PUMPING STATION

ITEM No. 1 :- REPLACEMENT OF SPARE PARTs

1

Supply of following Spare Part / Components for 600 HP FLOWMORE VT Pump Set Model 22HN / 2stage etc complete as per detailed specifications & as directed by Engineer-In-Charge. 1. Line Shaft Sleeve-1 no, 2.Line Shaft Bearing-1 no, 3.Gasket-1no, 4. Top Shaft-1 no, 5. Top Shaft Sleeve-1 no, 6. Line Shaft- 1 no, 7. O Ring- 1 no, 8. Gasket Champion Make- 1 no, 9. Radial Ball Bearing- 1 no, 10. Gib Key- 1 no, 11. HX,HD BOLT- 10 nos, 12. Retaining Washer- 10 nos, 13. PIN BLOCK- 10 nos, 14. Rubber Bush- 10 nos, 15. Nylock Nut- 10 nos, 16. SPH. ROLLER THRUST BEARING- 1 no, 17. Drive end Bearing- 1 no, 18. Non Drive end Bearing- 1 no



शहर अभियंता
मिरा-भाईंदर महानगरपालिका

जा.क्र.मनपा/पा.पु.व मलनि/१६७५/२०२५-२६
दि. १०/०६/२०२५.