



# मिरा-भाईदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईदर (प.), ता. ठाणे - 401 101 दुरध्वनी क्र. 28192828

पाणी पुरवठा व मलनिःसारण विभाग



जा.क्र.मिभा/मनपा/पा.पु.व मलनि/क.अ.६/१८०६/२०२५-२६

दि.२०/०६/२०२५

प्रति,  
सिस्टम मॅनेजर  
संगणक विभाग  
मिरा-भाईदर महानगरपालिका

विषय :- मिरा भाईदर महानगरपालिका क्षेत्रातील मलनिःसारण केंद्र क्र.4 मधील MCC पॅनल मधील घटकांचा पुरवठा, बसविणे, चाचणी व कार्यान्वयित करणेकरीता ऑनलाईन दर मागविणेबाबत.

मिरा भाईदर महानगरपालिका क्षेत्रातील मलनिःसारण केंद्र क्र.4 मधील MCC पॅनल मधील घटकांचा पुरवठा, बसविणे, चाचणी व कार्यान्वयित करणे कामाची निविदा मागविणेकरीता अंदाजपत्रक तयार करावयाचे आहे. परंतु सदर कामाअंतर्गत नमुद बाबींकरीताचे दर दरसुचीमध्ये उपलब्ध नसल्याने ऑनलाईन दर [www.mbmc.gov.in](http://www.mbmc.gov.in) या संकेत स्थळावर मागविणे करीता सोबत जोडलेल्या बाबींचा तक्ता ऑनलाईन प्रसिद्ध करण्यात यावा.

शहर अभियंता  
मिरा-भाईदर महानगरपालिका



# मिरा-भाईदर महानगरपालिका

पाणी पुरवठा व मलनिसारण विभाग

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईदर(प)

ता. जि.ठाणे - ४०१ १०१



मिरा भाईदर महानगरपालिका क्षेत्रातील मलनिःसारण केंद्र क्र.4 मधील MCC पॅनल मधील घटकांचा पुरवठा, बसविणे, चाचणी व कार्यान्वयित करणे कामी मिरा-भाईदर महानगरपालिका खालील तक्त्यातील बाबींकरिता ऑनलाईन दर मागवीत आहे.

उपरोक्त कामांतर्गत बाबींचे दर दि. 24.09.2025 ते दि. 01.10.2025 रोजी दुपारी 12.00 वाजेपर्यंत watersupply@mbmc.gov.in या ई-मेलवर पाठविण्यात यावे.

DESCRIPTION OF WORK	Aprox Qty	Unit	Rate (Excluding GST)
Refurbishment and upgradation of existing burned MCC panel at 12 MLD STP NO.4 by reusing existing sheet steel enclosure with surface preparation and powder coating, dismantling of all damaged parts and replacement with new incoming metering section (MCCB/ACB, CTs, meters, selector switches, indicating lamps etc.), provision of all motor starters (DOL and Star-Delta) with suitable contactors, overload relays, timers and protective devices, complete rewiring with copper conductors and ferrules, Laying of all burnt LT power and control cables with new XLPE/PVC insulated armored cables including dressing, glanding, termination and testing, and PLC Feedback control wiring with Marshaling Cabinet of all connected STP equipment (pumps, agitators, conveyor, screen and auxiliaries) with auto and manual provision, including supply of all materials, labor, installation, testing, commissioning, transport and incidental charges complete as per IS/IEC standards.	1		

शहर अभियंता

मिरा-भाईदर महानगरपालिका

जा.क्र.मनपा/पा.पु.व मलनि/१७०९/२०२५-२६

दि. २४/०९/२०२५