



## मिरा-भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

पाणी पुरवठा व मलनिःसारण विभाग

संकेतस्थळ - [www.mbmc.gov.in](http://www.mbmc.gov.in)

ई-मेल - [watersupply@mbmc.gov.in](mailto:watersupply@mbmc.gov.in)

संपर्क - 281922828-251



जा.क्र.मनपा/पापु व मलनि/ 9349 /2024-25

दि. 26/01/2024

प्रति,

सिस्टम मॅनेजर

संगणक विभाग

मिरा-भाईंदर महानगरपालिका

विषय :- मिरा भाईंदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे.

मिरा भाईंदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे या कामाची निविदा मागविणेकरीता अंदाजपत्रक तयार करावयाचे आहे. परंतु सदर कामा अंतर्गत लागणाऱ्या खालील बाबींकरीताचे दर दरसूचीमध्ये उपलब्ध नसल्याने त्यांचे ऑन-लाईन दर मागविणे आवश्यक आहे. याकरीता लागणाऱ्या बाबींचा तक्ता सोबत जोडत आहे, सदर तक्ता मनपाच्या [www.mbmc.gov.in](http://www.mbmc.gov.in) या संकेत स्थळावर प्रसिध्द करण्यात यावा.

शहर अभियंता

मिरा-भाईंदर महानगरपालिका





## मिरा-भाईंदर महानगरपालिका

पाणी पुरवठा व मलनिसारण विभाग

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

ता. जि.ठाणे - 401 101



मिरा भाईंदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे या कामाचे अंदाजपत्रक तयार करणेकमी मिरा-भाईंदर महानगर पालिका खालील तक्त्यातील बाबींकरिता ऑनलाईन दर मागवीत आहे.


उपरोक्त कामांतर्गत बाबींचे दर दि. 30.09.2024 ते दि. 07.10.2024 रोजी दुपारी 12.00

वाजेपर्यंत [watersupply@mbmc.gov.in](mailto:watersupply@mbmc.gov.in) या ई-मेलवर पाठविण्यात यावे.

Sr.N o.	DESCRIPTION OF WORK	QTY	Unit	Rate (Excluding GST)
1	<b>REPAIRs TO VALVE ACTUATOR</b> Supply, Installation, Testing & Commissioning Including Service engineer visit For Replacement of body casing for Actuator with reinstallation of 200 NB Butterfly Auto valve etc Complete as per detailed specifications and as instructed by Engineer-In-Charge	1	JOB	
2	<b>CHEMICAL DOSING TANK</b> Supply, Installation, Testing & Commissioning with Test & Trial of Chemical Dosing Tank of 200 litres capacity with required nozzles along with required & Material with re-Installation for Dosing pimps etc complete as per detailed specifications and as instructed by Engineer-In-Charge	3	NOS	
3	<b>CCTV MONITORING SYSTEM</b> Repairs, Rectification, Reconditioning & Re-commissioning of Existing CCTV monitoring system along with replacement of cameras and cables etc complete as per detailed specifications and as instructed by Engineer-in-Charge	1	JOB	
4	<b>AIR CONDITIONING SYSTEM</b> Repairs, Rectification, Reconditioning & Re-commissioning of Air conditioning System at PLC room - 3 tons capacity with required coolant gas etc complete as per detailed specifications and as instructed by Engineer-In-Charge	1	JOB	



5	<b>VOLTAGE STABILISER</b>	1	JOB	
	Repairs, Rectification, Reconditioning & Re-commissioning of Volage Stabiliser for UPS Invertor with all required material etc complete as per detailed specifications and as instructed by Engineer in Charge			
6	<b>CPU WITH LICENSE KEY</b>	1	JOB	
	Supply, Installation, Testing, Comissioning along with service engineer visit fir test & trial of CPU Dell Make of 16 GB RAM of 502 GB SSI hard disk for replacement Existing crashed CPU of 8 GB RAM of 126 GB normal hard disk. Reinstallation, reconfiuration and commissioning of PLC with License ket over desktop of new CPU etc complete as per detailed specifications and as instructed by Engineer-In-Charge			



शहर अभियंता

मिरा-भाईंदर महानगरपालिका

जा.क्र.मनपा/पा.पु.व मलनि/139/2024-25

दि.