OK

मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/ ९२ /2024-25
दि. ०८/१० /2024

प्रति,
जनसंपर्क अधिकारी
जनसंपर्क विभाग
मिरा भाईंदर महानगरपालिका

विषय :- जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

15 व्या वित्त आयोगातंर्गत मंजुर नागरी आयुष्यमान आरोग्य मंदिर सुरु करणे कामी बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload व सदर जाहिर सुचना हे पत्र मिळाल्यापासुन दोन दिवसात व्रतपत्रात प्रसिध्द करण्यात यावी.

कार्यकारी अभियंता (साबां/ विद्युत)
मिरा भाईंदर महानगरपालिका

मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/ ९२ /2024-25
दि. ०८/१० /2024

प्रति,
सिस्टीम मॅनेजर
माहिती तंत्रज्ञान विभाग
मिरा भाईंदर महानगरपालिका

विषय :- जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

15 व्या वित्त आयोगातंर्गत मंजुर नागरी आयुष्यमान आरोग्य मंदिर सुरु करणे. बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

कार्यकारी अभियंता (साबां/ विद्युत)
मिरा भाईंदर महानगरपालिका

मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्रं.२८१९२८२८

बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/ ९२ /2024-25
दि. ०८/१० /2024

// जाहिर नोटीस //

15 व्या वित्त आयोगातंर्गत मंजुर नागरी आयुष्यमान आरोग्य मंदिर सुरु करणे कामी चालु जिल्हा दरसुचीमध्ये दर उपलब्ध नसल्यामुळे खुल्या बाजारातुन दरपत्रक मागविण्यात येत आहे.

सदर कामाकरिता दि.14/10/2024 रोजी संध्या 4.00 वाजेपर्यंत मिरा भाईंदर महानगरपालिका, मुख्य कार्यालय, बांधकाम विभाग, 4 था मजला येथे स्वारस्य असलेल्या कंत्राटदाराने सोबत जोडलेल्या दरपत्रकातील बाबींकरीता दर भरुन देण्यात यावेत.

कार्यकारी अभियंता (साबां/ विद्युत)
मिरा भाईंदर महानगरपालिका

PC-07/24-25/PW/जाहिर सुचना-1

MIRA BHAINDAR MUNICIPAL CORPORATION
Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,
Bhaindar (W) 401101, Tal. Dist - Thane, 28192828
PWD/ELECTRIC DEPARTMENT

// RATE FORM //

Name of Work :- Proposed Work for Ayushyaman Aarogya Mandir in MBMC Area.

Name and address of Contractor :-

SR.NO.	ITEM		QTY	UNIT	RATE (All Taxes Included)
1.	Supplying installation of Fabricated GI Portable Cabin of Size 25 feet Length x 20 feet in Width x 8.60 feet Height including following Specifications		1	No	
	Bottom Frame -	100mm x 50 mm "I-beam Channel			
	Top Frame	50mm x 50 mm ms.Sq.pipe			
	Stiffener Bottom	100mm x 50 mm "I-beam Channel			
	Stiffener Top	40x20mm sq.pipe			
	Side post	75mm x 75mm ms.Sq.pipe			
	Ms SQ Pipe	2 mm thickness			
	Paneling Outside	Specially 1mm GI Sheet (make-Jsw, eassar, Asian,)			
	Interanal wall panelling	8 mm MDF SHEET			
	Roof Outside	1 mmGI sheet – (make :- jws, eassar, Asian, tata) Thick Properly Slopedand water tight, damber sheet also			
	False ceiling	8 mm MDF SHEET			
	Bottom Flooring	18MM CEMENT FIBER BOARD WITH VINYL CARPET (MAKE :-V BOARD, EVAREST BOARD, SHYADRI BOARD)			
	Sliding Door	Door with MS Structure 40'x20' Sq Pipe			
	Insulation	Glass Wool density of 1 kg/m3 (Ceiling and wall- 25mm) (Side Wall-16kg)			
	wiring	All wiring shall be concealed type shall be of polycab insulated wire			
	Electrical fitting	All electrical fittings in the Portable Cabin shall be 220-240 AC 50Hz led light, Door Light, Fan, Switches, Sockets, Telephone, Air Conditioners Point (MCB) (All Type of			

		Window Air Conditioning Systems as desired upon can be installed. (ISI BRAND switch sockets)			
	Earthing	Earthing point shall be provided for safety			
	Outside Painting	Painting with 1 coat of Primer with 2 coats of Epoxy paint.			
	Logo	Externl Branding Logo Painting			
	Hook	Specially formed Hooks for Easy Lifting and Shifting.			
	Main Door	6'6x3" (1 Nos.)			
	Sliding Window with M.S.Grill 3' x	3'x3' (8 Nos.)			
	5 Amp.switch & socket	6 modular (14 Nos.)			
	Cabin fan	Std (11 Nos.)			
	Led Pannel Lights	20watt (19 Nos)			
	Split AC Prov.with 16amp Switch	3model (2 Nos.)			
	Bulk Head	Sts (01 Nos.)			
	Main Switchboard	3modular (2 Nos)			
	MCB with Earthling	Std. (01 Nos)			
	Partition (6'.5" Height)(5 Nos.)				
	ALL FITTING IN TOILET (4'x4') 02 Nos. EWC Fitting With jet Spray & Tab Washbasin With Tap 4 Nos., Mirror, Soap Disk, Towel Ring, & Including All Plumbing Work And 1 Nos. CFL, Exhaust fan, CFL, Light with Switchboard, Inside ACP sheet *EWC Set (02 Nos.)* *Wash Basin* (04 Nos.)				
	Installation				
	Sliding Door (04 Nos.)				
	Voltas AC (1.5 Tn)(02 Nos)				
	Table Size:- 4'x2' (05 Nos.)				
	Bed Size : 6'x2'.5" (02 Nos.)				
	Boss Chair (01 Nos.)				
	Small Chairs (07 Nos.)				
	Medium Chair (03 Nos)				
	Three Seater Chair (02 Nos.)				
	File Storage (Pharmacy Room) (01 Nos.)				
	File Storage (In Doctor Room) (01 Nos)				
	File Storage (In Treatment Room) (01 Nos.)				
	Fule Storage (Concealing Room) (01 Nos)				
	Main Enterance Ramp (01)				
	INCLUDING				
	LED Light (19 Nos.)				
	MCB (01 Nos.)				
	Window With Grill Size: 3'x3' (08 Nos)				

	Main Board (07 Nos.)			
	Bulk Head (01 Nos.)			
	Transport Included			
	Unloading Included			
	Instalation Included			
	GST Included			

कंपनीचा सही व शिक्का