



मिरा-भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

पाणी पुरवठा व मलनिःसारण विभाग

संकेतस्थळ - www.mbmcc.gov.in

ई-मेल - watersupply@mbmcc.gov.in

संपर्क - 281922828-251



जा.क्र.मनपा/पापु व मलनि/ 1783/2024-25

दि.08/11/2024

प्रति,

सिस्टम मॅनेजर

संगणक विभाग

मिरा-भाईंदर महानगरपालिका

विषय :- मिरा भाईंदर महानगरपालिकेच्या साकेत पंप हाऊस येथील पंप क्र. 2 आणि फाटक येथील पंप क्र. 2 व 3 च्या VFD PANEL ची दुरुस्ती करणे या कामाचे अंदाजपत्रक तयार करणेकमी ऑनलाईन दर मागविणेबाबत

मिरा भाईंदर महानगरपालिकेच्या साकेत पंप हाऊस येथील पंप क्र. 2 आणि फाटक येथील पंप क्र. 2 व 3 च्या VFD PANEL ची दुरुस्ती करणे कामाचे अंदाजपत्रक तयार करावयाचे आहे. परंतु सदर कामा अंतर्गत लागणाऱ्या खालील बाबींकरीताचे दर दरसुचीमध्ये उपलब्ध नसल्याने त्यांचे ऑन-लाईन दर मागविणे आवश्यक आहे. याकरीता लागणाऱ्या बाबींचा तक्ता सोबत जोडत आहे, सदर तक्ता मनपाच्या www.mbmcc.gov.in या संकेत स्थळावर प्रसिध्द करण्यात यावा.

शहर अभियंता

मिरा-भाईंदर महानगरपालिका



मिरा-भाईंदर महानगरपालिका

पाणी पुरवठा व मलनिसारण विभाग

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

ता. जि.ठाणे - 401 101




मिरा भाईंदर महानगरपालिकेच्या साकेत पंप हाऊस येथील पंप क्र. 2 आणि फाटक येथील पंप क्र. 2 व 3 च्या VFD PANEL ची दुरुस्ती करणे या कामाचे अंदाजपत्रक तयार करणेकमी मिरा-भाईंदर महानगर पालिका खालील तक्त्यातील बाबींकरिता ऑनलाईन दर मागवीत आहे.

उपरोक्त कामांतर्गत बाबींचे दर दि. 8.11.2024 ते दि. 15.11.2024 रोजी दुपारी 12.00 वाजेपर्यंत watersupply@mbmc.gov.in या ई-मेलवर पाठविण्यात यावे.

SR. NO.	DESCRIPTION	QTY	UNIT	RATE (Excluding GST)
Repairs of Siemens VFD Panel no 2 at Saket Water Pumping station				
1	CIM Control Interface Module- (G130, S120)	1	NOS	
2	Fan (complete assembly kit) for AC Drive/Power/Motor Module Frame sizes G, H and J	2	NOS	
3	Fan transformer for 3ac 380-480 v framesize H	1	NOS	
4	THYR_TZ800N 1800V 800A	6	NOS	
5	IGD3/R2 mod. 480V/840A	3	NOS	
6	Capacitor 5200U 20% 400V 85C	24	NOS	
7	TDB BGR R6 480V AC (J2S309856)	1	NOS	
8	Cable set - rectifier/Inverter, FS-H Thyristor, PB inv temp sensor, PB rect temp, PS,	1	SET	
Repairs of Siemens VFD Panel no 2 & 3 at Phatak Water Pumping station				
1	POWER UNIT			
	Supplying, Installing, Testing & Commissioning of SINAMICS G120 POWER MODULE PM240-2 WITHOUT FILTER WITH BUILT IN BRAKING CHOPPER 3AC380-480V +10/-20% 47-63HZ OUTPUT HIGH OVERLOAD: 75KW FOR 200% 3S, 150% 57S, 100% 240S AMBIENT TEMP -20 TO +50 DEG C (HO) OUTPUT LOW OVERLOAD: 90KW FOR 150% 3S, 110% 57S, 100% 240S AMBIENT TEMP -20 TO +40 DEG C (LO) 708 X 305 X 357 (HXWXD), FSF PROTECTION IP20 WITHOUT CONTROL UNIT AND PANEL APPROVED FOR CU FIRMWARE- VERSION V4.7 HF8	2	NOS	

	CONTROL UNIT			
2	Supplying, Installing, Testing & Commissioning of SINAMICS G120 CONTROL UNIT CU240E-2 DP E-TYPE SAFETY INTEGRATED STO PROFIBUS DP 6DI, 3DO, 2AI, 2AO, MAX 1F-DI PTC/KTY INTERFACE USB- AND SD/MMC-INTERFACE PROTECTION IP20 AMBIENT TEMP 0 TO +50 DEG C WITHOUT POWER MODULE AND PANEL	2	NOS	
	INTELLIGENT OPERATOR PANEL IOP			
3	SINAMICS G Intelligent Operator Panel IOP-2 for SINAMICS G120, G120P G110M, G110D, G120D, G120C ET 200PRO FC-2 Language settings: German, English, French Italian, Spanish Portuguese, Dutch Swedish, Russian Czech, Polish Turkish, Finnish Chinese (simplified) Environmental class during operation: Harmful chemical substances, Class 3C3 according to IEC 60721-3-3: 2002 alongwith SINAMICS G120 door mounting kit IP55/ UL Type 12 for Intelligent Operator Panel IOP (IP54), IOP-2 (IP55) and Basic Operator Panel BOP-2 (IP55); contains seal fixing accessories and connecting cable (5 m)	2	NOS	


 शहर अभियंता
 मिरा-भाईंदर महानगरपालिका

जा.क्र.मनपा/पा.पु.व मलनि/1783/2024-25

दि. 08/11/2024