



# मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८

## बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/ 30

/2024-25

दि. 29/07/2024

प्रति,

जनसंपर्क अधिकारी

जनसंपर्क विभाग

मिरा भाईंदर महानगरपालिका

**विषय :-** जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

मिरा-भाईंदर महानगरपालिका हद्दीतील उद्याने विकसीत व सुशोभिकरण करणे बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका

८



# मिरा भाईदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८

## बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/ 30

/2024-25

दि. 19/07/2024

प्रति,

सिस्टीम मॅनेजर

माहिती तंत्रज्ञान विभाग

मिरा भाईदर महानगरपालिका

**विषय :-** जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

मिरा-भाईदर महानगरपालिका हद्दीतील उद्याने विकसीत व सुशोभिकरण करणे बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईदर महानगरपालिका

15



## मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८  
बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/३० /2024-25

दि. 29/07/2024

### // जाहिर नोटीस //

मिरा-भाईंदर महानगरपालिका हद्दीतील उद्याने विकसीत व सुशोभिकरण करणे कामी चालु जिल्हा  
दरसुचीमध्ये दर उपलब्ध नसल्यामुळे खुल्या बाजारातून दरपत्रक मागविण्यात येत आहे.

सदर कामाकरिता दि. 06/08/2024 रोजी संध्या 4.00 वाजेपर्यंत मिरा भाईंदर  
महानगरपालिका, मुख्य कार्यालय, बांधकाम विभाग, 4 था मजला येथे स्वारस्य असलेल्या  
कंत्राटदाराने सोबत जोडलेल्या दरपत्रकातील बाबींकरीता दर भरून देण्यात यावेत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका





**MIRA BHAINDAR MUNICIPAL CORPORATION**  
**PWD / Electrical Department**  
**Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,**  
**Bhaindar (W) 401101,**  
**Tal. Dist – Thane, Ph. 28192828**

**// RATE FORM //**

**Name of Work :- PROPOSED GARDEN DEVELOPMENT AND BEAUTIFICATION AT VARIOUS LOCATIONS IN MBMC AREA**

**Name and address of Contractor :-**

**B-2 FORM**

Sr. No.	Description	Qty	UNIT	RATE
1	Providing and fixing stone cladding(Rubble,malad,etc). on external face of the wall, with all the necessary materials along with finish in pigment, including all labour ,etc complete MR	1.00	SMT	
2	Providing & fixing in the footpath Combi- Paver having average crushing strength not less than 80 N/mm <sup>2</sup> as per technical specifications and IS Code 15658:2006; shot blasted 60mm thick in approved texture and colour and combination size 100 x 200, 125 x 200, 175 x 200, 225 x 200, 275 x 200 to be fixed on average compacted thickness 25 mm well graded sand cushioning uniformly compacted with proper capacity mechanical compactor with required level, grade and camber etc. complete as specified and as directed by the Engineer. NOTE: THIS ITEM SHOULD BE OPRATED ONLY AFTER SPECIFIC SANCTION OF DIR(E.S.& P.) or Equivalent. MR	1.00	SMT	
3	GRASS JOINT PAVING: Providing and laying machine cut machine polished kota stone flooring for Grass joint paving, 25mm to 30mm thick required width in plain pattern on bed of 1:6 C. M. including cement float, curing, polishing and cleaning including removing unwanted stuff as directed. Excavation for Planting of Lawn Digging of Soft surface up to 30 Cm. as per drawing and specification provided by Engineer In-charge. MR	1.00	SMT	

4	Aluminium Fins:- Providing and Fixing Horizontal fins with 3"x1" Aluminium Tubular Section Powder coated Horizontally with 1" facing and 3" Gap in to in in sections with 1"x1" Aluminium Angle powder coated fixed at top and bottom for fixing, with Hardware , with labour inclusive. MR	1.00	SMT	
5	SITC of Drip Irrigation system Including all related Materials , Drip Fittings + valve , Piping & Solutions material complete as per specification provided by the engineer Incharge MR	1.00	RMT	
6	Supply and installation of Vertical garden as per design with approved plants ,including the fabricated tray/stand/patterned fabrication with 2 coat of oil paint and necessary fittings to fix on Walls/pillars etc specification as per drawings and Engineer in charge Complete.MR	1.00	SMT	
7	ITEM NO 02 Providing & Installation of Filter system including Fittings charges for vertical garden,instatllation complete as per specification provided by the engineer Incharge MR	1.00	NOS	
8	Providing playing equipments for pets for play area including bolting ,fixing on PCC base /Foundation etc as per Approved materials and drawings specification provided by engineer incharge Complete MR			
	Wooden planks	1.00	NOS	
	Hurdle	1.00	NOS	
	Tunnel/Dog crawl	1.00	NOS	
	Stepping pads	1.00	NOS	
	Trampoline	1.00	NOS	
	Hoop jump	1.00	NOS	
	Platform climb	1.00	NOS	
9	Providing and fixing EPDM (Rubber Mat)(Ethylene propylene diene methylene) flooring for children play area of thickness 25-30 mm above PCC as per specification provided by engineer incharge MR	1.00	SMT	



10	Providing and laying of beach sand for children play area as per specification provided by engineer incharge MR	1.00	KG	
11	Providing and Fixing Wall mounted bicycle stand units as per drawings and specification provided by the engineer in charge. MR	1.00	NOS	
12	Providing and fixing Decorative themed FRP Based Gate (Sports,Musical,Historical Hero,Cultural) entrance of size as specification provided by engineer incharge.complete(5 mt width) MR	1.00	JOB	
13	Supplying and fixing Stone sculpture/statues of theme upto 1.8 mt ht of approved size and material complete as per specification provided by engineer inchargeMR	1.00	JOB	
14	Double Side Pvc Coated waterproof And Sunshed Tensile Fabric Tensile Roofing including strings and fabrication Specification as per engineer in charge and drawing. Complete with fittings MR	1.00	SMT	
15	Providing and Fixing laser cut 3-4 mm Acrylic letters of height upto 24 inches with, with all other necessary Hardware for fittings and Labour all Inclusive.including profile LED back lighting .complete MR	1.00	LETTERS	
16	Providing and fixing MBMC Logo on entrance gate MR	1.00	NOS	
17	Providing and fixing stainless steel Name Board on gate/Building including LED backlight complete as per drawing .size (6mx1m) MR	1.00	NOS	
18	Providing & Fixing of signage using 304 Stainless steel letters for the front & side fascia and 5mm thick acrylic molded letters, for back fascia moulded letters with height 24 inches, with necessary power supplies for connection, including profile LED back lighting MR	1.00	NOS	
19	Providing and Fixing laser cut 3 mm M.S. sheet letters of height 24 inches with studs weled at backside for fixing in wall with chemical grouting , all letters powder coated with all other necessary Hardware fittings and Labour all Inclusive.including profile LED back lighting MR	1.00	LETTERS	

20	Providing and fixing Internal signage ss brush finish 2 mm thick . Spec. As directed by Engineer-In-Charge. MR	1.00	NOS	
21	Providing and Installation Planter figure set of 3 having size 4 ft, made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication)MR	1.00	JOB	
22	Providing and installation Hand Model holding tress having size of 3ft ht 9ft wide made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
23	Providing and installation Sculpture/statute, ht of structure - 6ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
24	Providing and installation Sculpture/statue of freedom fighters, ht of structure - 8ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
25	Providing and installation decorative Sculpture, ht of structure - 6ft wide 4 ft ht made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication)MR	1.00	JOB	
26	Providing and Installation decorative Sculpture as per approved design, ht of structure - 8 ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
27	Providing and supplying themed seating area as per approved design, structure 7- 8 ft wide and 9-10 ft height made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
28	Providing and Installation thematic planter as per approved design, ht of structure 4 ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved	1.00	JOB	



	design complet as per specification provided by engineer incharge.(Including fabrication) MR			
29	Providing and Installation Signages as per approved design, ht of structure 5-6 ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication) MR	1.00	JOB	
30	Providing and Installation steps and seat out for play area as per approved design, ht of structure steps 4 ft length 5meter,sit out box 8ft X 8ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge.(Including fabrication)MR	1.00	JOB	
31	Providing and Installation themed shelter area with polycarbonated sheet as per approved design, ht of structure 12-15 ft, width- 5 to 6ft made of R.S.C.R (Fibre ) material with double PU gloss or matt finished coating with approved design complet as per specification provided by engineer incharge. (Including fabrication) MR	1.00	JOB	